

# EARTHWORK SCHEDULE

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**62302**  
\* (1818, ETC., 2324.6-1PIR-9)

STATION	TO STATION	EARTH EXCAVATION (CU YD)	EXCAVATE EXISTING GRANULAR MATERIAL (CU YD)	PLACE EXISTING GRANULAR MATERIAL (CU YD)	EXISTING GRANULAR MATERIAL BALANCE SURPLUS (+) OR SHORTAGE (-) (CU YD)
1367+00	1368+00	664	63		63
1368+00	1369+00	646	63		63
1369+00	1370+00	652	64		64
1370+00	1371+00	664	66		66
1371+00	1372+00	664	66		66
1372+00	1373+00	666	66		66
1373+00	1374+00	661	66		66
1374+00	1375+00	702	66		66
1375+00	1376+00	780	65		65
1376+00	1377+00	827	63		63
1377+00	1378+00	869	62		62
1378+00	1379+00	882	61		61
1379+00	1380+00	819	61		61
1380+00	1381+00	753	62		62
1381+00	1382+00	763	66		66
1382+00	1383+00	815	69		69
1383+00	1384+00	829	69		69
1384+00	1385+00	813	70		70
1385+00	1386+00	795	72		72
1386+00	1387+00	656	62		62
1387+00	1388+00	558	51		51
1388+00	1389+00	632	53		53
1389+00	1390+00	740	57		57
1390+00	1391+00	780	63		63
1391+00	1392+00	737	62		62
1392+00	1393+00	741	57		57
1393+00	1394+00	748	57		57
1394+00	1395+00	737	57		57
1395+00	1396+00	776	58		58
1396+00	1397+00	801	58		58
1397+00	1398+00	804	59		59
1398+00	1399+00	908	59		59
1399+00	1400+00	1034	59		59
1400+00	1401+00	1093	61		61
1401+00	1402+00	1133	63		63
1402+00	1403+00	1069	64		64
1403+00	1404+00	1224	61		61
1404+00	1405+00	1249	58		58
1405+00	1406+00	994	60		60
1406+00	1407+00	1044	58		58
1407+00	1408+00	929	54		54
1408+00	1409+00	650	54		54
1409+00	1410+00	594	56		56
1410+00	1411+00	637	59		59
1411+00	1412+00	684	61		61

SEE NOTE 4

STATION	TO STATION	EARTH EXCAVATION (CU YD)	EXCAVATE EXISTING GRANULAR MATERIAL (CU YD)	PLACE EXISTING GRANULAR MATERIAL (CU YD)	EXISTING GRANULAR MATERIAL BALANCE SURPLUS (+) OR SHORTAGE (-) (CU YD)
1412+00	1413+00	629	62		62
1413+00	1414+00	576	63		63
1414+00	1415+00	581	64		64
1415+00	1416+00	563	65		65
1416+00	1417+00	535	65		65
1417+00	1418+00	502	65		65
1418+00	1419+00	489	65		65
1419+00	1420+00	467	65		65
1420+00	1421+00	411	63		63
1421+00	1422+00	422	58		58
1422+00	1423+00	550	56		56
1423+00	1424+00	658	59		59
1424+00	1425+00	703	58		58
1425+00	1426+00	717	58		58
1426+00	1427+00	665	57		57
1427+00	1428+00	584	55		55
1428+00	1429+00	554	53		53
1429+00	1430+00	617	55		55
1430+00	1431+00	675	58		58
1431+00	1432+00	666	58		58
1432+00	1433+00	648	57		57
1433+00	1434+00	626	55		55
1434+00	1435+00	605	54		54
1435+00	1436+00	611	54		54
1436+00	1437+00	613	54		54
1437+00	1438+00	602	54		54
1438+00	1439+00	593	53		53
1439+00	1440+00	580	53		53
1440+00	1441+00	573	53		53
1441+00	1442+00	588	53		53
1442+00	1443+00	599	53		53
1443+00	1444+00	721	53		53
1444+00	1445+00	858	64		64
1445+00	1446+00	865	78		78
1446+00	1447+00	808	83		83
1447+00	1448+00	920	88		88
1448+00	1449+00	1029	89		89
1449+00	1450+00	1022	93		93
1450+00	1451+00	1061	96	320.3	-224
1451+00	1452+00	997	94	366.3	-272
1452+00	1453+00	929	91	349.8	-258
1453+00	1454+00	875	90	336.1	-246
1454+00	1455+00	819	84	316.1	-232
1455+00	1456+00	763	78	300.6	-223
1456+00	1457+00	708	73	285.9	-213

SEE NOTE 4

STATION	TO STATION	EARTH EXCAVATION (CU YD)	EXCAVATE EXISTING GRANULAR MATERIAL (CU YD)	PLACE EXISTING GRANULAR MATERIAL (CU YD)	EXISTING GRANULAR MATERIAL BALANCE SURPLUS (+) OR SHORTAGE (-) (CU YD)
1457+00	1458+00	684	70	273.5	-203
1458+00	1459+00	672	69	267.4	-199
1459+00	1460+00	679	69	277.4	-208
1460+00	1461+00	673	69	286.5	-217
1461+00	1462+00	647	68	260.4	-193
1462+00	1463+00	670	67	253.0	-186
1463+00	1464+00	707	67	262.6	-195
1464+00	1465+00	695	66	252.0	-186
1465+00	1466+00	684	66	248.0	-182
1466+00	1467+00	688	66	248.7	-183
1467+00	1468+00	687	76	249.8	-174
1468+00	1469+00	689	76	248.0	-172
1469+00	1470+00	702	66	246.5	-180
1470+00	1471+00	740	67	253.1	-186
1471+00	1472+00	778	69	260.4	-192
1472+00	1473+00	774	69	260.6	-192
1473+00	1474+00	792	69	263.0	-194
1474+00	1475+00	892	70	294.8	-225
1475+00	1476+00	898	69	294.6	-226
1476+00	1477+00	820	67	264.3	-197
1477+00	1478+00	782	66	259.8	-194
1478+00	1479+00	747	66	255.6	-190
1479+00	1480+00	731	65	255.0	-190
1480+00	1481+00	724	66	254.8	-188
1481+00	1482+00	723	68	253.0	-185
1482+00	1483+00	712	68	250.2	-182
1483+00	1484+00	688	67	245.0	-178
1484+00	1485+00	674	67	242.8	-176
1485+00	1486+00	677	67	245.2	-178
1486+00	1487+00	694	67	246.5	-179
1487+00	1488+00	709	67	247.8	-181
1488+00	1489+00	709	67	249.8	-183
1489+00	1490+00	702	68	256.7	-189
1490+00	1491+00	688	69	261.9	-193
1491+00	1492+00	681	69	264.4	-195
1492+00	1493+00	693	70	265.6	-196
1493+00	1494+00	710	70	263.9	-194
1494+00	1495+00	702	70	263.9	-194
1495+00	1496+00	691	70	265.6	-195
1496+00	1497+00	698	70	268.7	-198
1497+00	1498+00	715	70	270.6	-200
1498+00	1499+00	714	69	264.6	-196
1499+00	1500+00	689	68	257.0	-189
1500+00	1501+00	686	68	257.6	-190
1501+00	1502+00	673	66	249.6	-184

EW-01

REVISIONS	
NAME	DATE
ADDENDUM 1	8/12/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
31ST STREET TO 71ST STREET  
SB EXPRESS LANE RECONSTRUCTION  
EARTHWORK SCHEDULE

SCALE: 1"=N.T.S.      DRAWN BY: KAR  
DATE: 07/07/05      CHECKED BY: DDM

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
Chicago, Illinois  
312 228 0100  
www.bbairc.com

11/13/04 AM 8/19/2005