

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	598	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62302 \*1818, ETC, 2324.6-1P1R-9

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN		90% FEDERAL / 10% STATE							
			TOTAL QUANTITY	ROADWAY J000-2A	RETAINING WALLS Y007	S.N. 016-2625 X928-2A	SIGNING Y002-1C	SAFETY SFTY-3N	LIGHTING Y030-1E	SURVEILLANCE Y032-1F	BRIDGE REPAIRS SFTY-2A	
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	17,324	17,324								
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	3,916	3,916								
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	58,401	58,401								
70400100	TEMPORARY CONCRETE BARRIER	FOOT	20,343	20,343								
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	27,405	27,405								
72000100	SIGN PANEL - TYPE 1	SQ FT	676				676					
72000200	SIGN PANEL - TYPE 2	SQ FT	227				227					
72000300	SIGN PANEL - TYPE 3	SQ FT	2,242				2,242					
72100100	SIGN PANEL OVERLAY	SQ FT	3				3					
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	64				64					
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1244				1244					
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	948				948					
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3,150				3,150					
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	88				88					
73000100	WOOD SIGN SUPPORT	FOOT	1,070				1,070					
73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	217				217					
73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	137				137					
73302210	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (36" X 7'-0")	FOOT	62				62					
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	84				84					
73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	271				271					
73400100	CONCRETE FOUNDATIONS	CU YD	10	10								
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	223	223								
73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	9				9					
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	2				2					
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	18	18								
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	254	254								
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	104,855	104,855								
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	27,987	27,987								
78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	20,967	20,967								
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	5,511	5,511								
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	1061	1061								
78200530	BARRIER WALL MARKERS, TYPE C	EACH	445	445								
78201000	TERMINAL MARKER, DIRECT APPLIED	EACH	1	1								
78300100	PAVEMENT MARKING REMOVAL	SQ FT	29,997	29,997								

00 - SFTY - 3C  
 \* - SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94/90 (DAN RYAN EXPRESSWAY)  
 31ST STREET TO 71ST STREET  
 SB EXPRESS LANE RECONSTRUCTION  
 SUMMARY OF QUANTITIES  
 SCHEDULE

SCALE: NTS  
 DATE: 07/07/05

DRAWN BY: RA  
 CHECKED BY: JDC

Rev. 9-19-05  
 Rev. 8-31-05

BOWMAN, BARRETT & ASSOCIATES INC.  
 CONSULTING ENGINEERS  
 Chicago, Illinois  
 312.228.0100  
 www.bbainc.com

S00-04

6/29/2005 5:37:29 PM