

| | | | | | | | |
|---|---------|----------------|----------------|-------|----------|-----------|----|
| LOCATION NO. | 1 | STATE I.D. NO. | 3S0501039L61.2 | | | | |
| COUNTY | LASALLE | ROUTE | FAI 39 | M.P. | 61.2 | DIRECTION | SB |
| DESCRIPTION OF WORK | | | | UNIT | QUANTITY | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | | | | EACH | 1 | | |
| REMOVE AND REINSTALL SIGN PANEL | | | | SO FT | 302 | | |
| REMOVE AND REINSTALL WALKWAY | | | | FOOT | 32 | | |
| REMOVE OVERHEAD SIGN STRUCTURE - SPAN | | | | EACH | 1 | | |
| OVERHEAD SIGN STRUCTURE - SPAN TYPE III-A (5'-0" x 7'-0") | | | | FOOT | 108 | | |
| FURNISH AND INSTALL SAFETY CHAIN | | | | EACH | 2 | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | | | | EACH | 5 | | |
| REPLACE/TIGHTEN CLIP PER SIGN | | | | EACH | 2 | | |
| REPLACE U-BOLT (DAMPER) | | | | EACH | 2 | | |

| | | | | | | | |
|---|--------|----------------|------------------|-------|----------|-----------|----|
| LOCATION NO. | 2 | STATE I.D. NO. | 3S0321080L0112.2 | | | | |
| COUNTY | GRUNDY | ROUTE | FAI 80 | M.P. | 112.2 | DIRECTION | WB |
| DESCRIPTION OF WORK | | | | UNIT | QUANTITY | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | | | | EACH | 1 | | |
| REMOVE AND REINSTALL SIGN PANEL | | | | SO FT | 391 | | |
| REMOVE AND REINSTALL WALKWAY | | | | FOOT | 54 | | |
| REMOVE OVERHEAD SIGN STRUCTURE - SPAN | | | | EACH | 1 | | |
| OVERHEAD SIGN STRUCTURE - SPAN TYPE III-A (5'-0" x 7'-0") | | | | FOOT | 103 | | |
| REPLACE/TIGHTEN CLIP PER SIGN | | | | EACH | 4 | | |

| | | | | | | | |
|---|--------|----------------|-----------------|-------|----------|-----------|----|
| LOCATION NO. | 3 | STATE I.D. NO. | 3C0321080L118.7 | | | | |
| COUNTY | GRUNDY | ROUTE | FAI 80 | M.P. | 118.7 | DIRECTION | WB |
| DESCRIPTION OF WORK | | | | UNIT | QUANTITY | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | | | | EACH | 1 | | |
| REMOVE, STORE AND RE-ERECT SIGN PANEL | | | | SO FT | 78 | | |
| REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |
| REMOVE AND REINSTALL WALKWAY | | | | FOOT | 16 | | |
| REMOVE CONCRETE FOUNDATION - OVERHEAD | | | | EACH | 1 | | |
| DRILLED SHAFT CONCRETE FOUNDATIONS | | | | CU YD | 6.8 | | |
| OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" x 5'-6") | | | | FOOT | 30 | | |
| FURNISH AND INSTALL SAFETY CHAIN | | | | EACH | 2 | | |
| RELOCATE ELECTRIC SERVICE | | | | EACH | 1 | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | | | | EACH | 4 | | |
| FURNISH AND INSTALL WALKWAY TIE DOWN BOLTS | | | | EACH | 2 | | |
| REPLACE/TIGHTEN CLIP PER SIGN | | | | EACH | 4 | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |

| | | | | | | | |
|---|----------|----------------|-----------------|-------|----------|-----------|----|
| LOCATION NO. | 4 | STATE I.D. NO. | 3C0381057R268.0 | | | | |
| COUNTY | IROQUOIS | ROUTE | FAI 57 | M.P. | 268.0 | DIRECTION | NB |
| DESCRIPTION OF WORK | | | | UNIT | QUANTITY | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | | | | EACH | 1 | | |
| REMOVE, STORE AND RE-ERECT SIGN PANEL | | | | SO FT | 78 | | |
| REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |
| REMOVE AND REINSTALL WALKWAY | | | | FOOT | 17 | | |
| REMOVE CONCRETE FOUNDATION - OVERHEAD | | | | EACH | 1 | | |
| DRILLED SHAFT CONCRETE FOUNDATIONS | | | | CU YD | 6.1 | | |
| OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" x 5'-6") | | | | FOOT | 30 | | |
| FURNISH AND INSTALL SAFETY CHAIN | | | | EACH | 2 | | |
| RELOCATE ELECTRIC SERVICE | | | | EACH | 1 | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | | | | EACH | 4 | | |
| FURNISH AND INSTALL WALKWAY TIE DOWN BOLTS | | | | EACH | 4 | | |
| REPLACE/TIGHTEN CLIP PER SIGN | | | | EACH | 4 | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |

| | | | | | | | |
|---|----------|----------------|-----------------|-------|----------|-----------|----|
| LOCATION NO. | 5 | STATE I.D. NO. | 3C0381057R269.3 | | | | |
| COUNTY | IROQUOIS | ROUTE | FAI 57 | M.P. | 269.3 | DIRECTION | SB |
| DESCRIPTION OF WORK | | | | UNIT | QUANTITY | | |
| DISCONNECT/RECONNECT ELECTRIC SERVICE | | | | EACH | 1 | | |
| REMOVE, STORE AND RE-ERECT SIGN PANEL | | | | SO FT | 78 | | |
| REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |
| REMOVE OVERHEAD SIGN STRUCTURE WALKWAY | | | | FOOT | 17 | | |
| REMOVE CONCRETE FOUNDATION - OVERHEAD | | | | EACH | 1 | | |
| DRILLED SHAFT CONCRETE FOUNDATIONS | | | | CU YD | 6.1 | | |
| OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" x 5'-6") | | | | FOOT | 30 | | |
| OVERHEAD SIGN STRUCTURE - WALKWAY | | | | FOOT | 17 | | |
| FURNISH AND INSTALL SAFETY CHAIN | | | | EACH | 2 | | |
| RELOCATE ELECTRIC SERVICE | | | | EACH | 1 | | |
| REPLACE/TIGHTEN CLIP PER SIGN | | | | EACH | 4 | | |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - CANTILEVER | | | | EACH | 1 | | |