


For anchor rod size and placement, see Support Frame Detail Sheet.

Anchor rod shall be ground or filed to bright metal at clamp and cable connection location.



BAR LIST - EACH FOUNDATION

Bar	Number	Size	Length	Shape
v4(E)	24	#9	F less 5"	—
#4 bar spiral (E) - see Side Elevation				

NOTES:

The foundation dimensions shown are based on the presence of mostly cohesive soils with an average Unconfined Compressive Strength (Qu) of at least 1.25 tsf, which must be determined by previous soil investigations at the jobsite. When other conditions are indicated, the boring data will be included in the plans and the foundation dimensions shown will be the result of site specific designs.


If the conditions encountered are different than those indicated, the Contractor shall notify the Engineer to determine if the foundation dimensions need to be modified. If dimensions "B" or "F" are revised by more than 12" by the Contractor, "as-built" plans shall be prepared and submitted to the District Bureau of Operations for future reference.

No sonotubes or decomposable forms shall be used below the lower conduit entrance. Permanent metal forms or other welding may not be left in place below that elevation without the Engineer's written permission.

Concrete shall be placed monolithically, without construction joints.

Backfill shall be placed per Article 502 of Standard Specification and prior to erection of support column.

A normal surface finish followed by a Bridge Seat Sealer application will be required on concrete surfaces above the lowest elevation 6" below finished ground line. Cast included in Drilled Shaft Concrete Foundation.



Structure Number	Station	Left Foundation					Right Foundation					Class DS Concrete (Cu. Yds.)
		Elevation Top	Elevation Bottom	A	B	F	Elevation Top	Elevation Bottom	A	B	F	
1 2S0371080R007.9	453+16	101.00	81.50	3.0	16.5	19.5	101.00	82.50	2.2	16.5	18.7	20.0
2 2S0811088L017.3	323+16	103.00	82.80	3.7	16.5	20.2	103.00	84.50	2.0	16.5	18.5	20.2
3 2S0815092R026.0	517+21	100.00	76.30	3.2	20.5	23.7	100.00	77.10	2.4	20.5	22.9	24.2
4 2S0811074L001.3	296+21	104.00	85.50	2.0	16.5	18.5	99.00	79.50	3.0	16.5	19.5	19.9

- 1 Benchmark 100.00 on top of concrete NW footing of existing sign
- 2 Benchmark 100.00 on top of concrete SW corner of NE footing of existing sign
- 3 Benchmark 100.00 on top of concrete east foundation of existing sign
- 4 Benchmark 100.00 top of concrete NE corner of the NW foundation of existing sign

NUMBER	REVISION	DATE

**DETAILS FOR 10" Ø SUPPORT FRAME
TYPE I-A or II-A TRUSS**

**OVERHEAD SIGN STRUCTURES
DRILLED SHAFT DETAILS**

OS4-F3

12-1-08

FILE NAME =	USER NAME = linkdj	DESIGNED -	REVISED -
D:\BR\SIGN TRUSS\CADD Plans\2811 contr\2811 plans.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Tue Aug 03 06:42:28 2010		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DISTRICT 2 SIGN
STRUCTURE REPLACEMENT

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	VARIOUS	27	15
CONTRACT NO. 46132			ILLINOIS FED. AID PROJECT	