

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

District 1
Schedule of Overhead Sign Structure Repair & Replacement

Location No.:	1-01	State I.D. No.:	1C016I094R034.0 (CLE-2) M2		
County:	Cook	Route:	I-94	M.P.:	34.0
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure - Cantilever	Each	1.00			
Remove Concrete Foundation - Overhead	Each	1.00			
Overhead Sign Structure - Cantilever Type III	FT	35.00			
Overhead Sign Structure Walkway	FT	33.50			
Concrete Foundation	CU YD	3.30			
Remove & Reinstall Sign Panel	SQ FT	196.00			

Location No.:	1-02	State I.D. No.:	1S049U41L000.0 (TDR-1) LP2		
County:	Lake	Route:	US-41	M.P.:	0.0
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure Span	Each	1.00			
Overhead Sign Structure Span Type II-A	Foot	61.00			
Rebuild Concrete Foundation for Overhead Sign Structure	Each	2.00			
Remove & Reinstall Sign Panel	SQ FT	331.12			
Overhead Sign Support Grout Repair	Each	4.00			
Overhead Sign Structure Walkway (internal)	Foot	35.50			

Location No.:	1-03	State I.D. No.:	1S016I094R000.0 (S3) T1		
County:	Cook	Route:	I-94	M.P.:	0.0
Direction:					
Description of Work	Unit	Quantity			
Remove & Re-erect Overhead Sign Span	Each	1.00			
Structural Steel Sign Support Overhead Sign Structure	Each	2.00			
Furnish & Install Saddle Shim Block	Each	4.00			
Furnish & Install Internal Truss Damper	Each	1.00			
Overhead Sign Structure Walkway (internal)	Foot	60.00			
Overhead Sign Support Grout Repair	Each	4.00			

Location No.:	1-04	State I.D. No.:	1S016I094R028.8 (TRS-2) T4		
County:	Cook	Route:	I-94	M.P.:	28.8
Direction:	SB				
Description of Work	Unit	Quantity			
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00			
Structural Steel Sign Support Overhead Sign Structure	Each	2.00			
Saddle Shim Block	Each	4.00			
Furnish & Install Internal Truss Damper	Each	1.00			
Overhead Sign Structure Walkway(internal)	Foot	90.00			

Location No.:	1-05	State I.D. No.:	1S016I094R040.8 (TRE-1) D2		
County:	Cook	Route:	I-94	M.P.:	40.8
Direction:	SB				
Description of Work	Unit	Quantity			
Remove & Re-erect Overhead Sign Structure-Span	Each	1.00			
Structural Steel Sign Support Overhead Sign Structure	Each	2.00			
Furnish & Install Saddle Shim Block	Each	4.00			
Furnish & Install Internal Truss Damper	Each	1.00			
Overhead Sign Structure Walkway(internal)	Foot	77.00			

Location No.:	1-06	State I.D. No.:	1S016I094R041.4 (RS-1) C2		
County:	Cook	Route:	I-94	M.P.:	41.4
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure-Span	Each	1.00			
Overhead Sign Structure Span Type II-A	Foot	73.00			
Rebuild Concrete Foundation for Overhead Sign Structure	Each	2.00			
Remove & Reinstall Sign Panel	SQ FT	444.00			
Overhead Sign Structure Walkway(internal)	Foot	58.00			

Location No.:	1-07	State I.D. No.:	1S016I094R039.7 (ETS-11) E2		
County:	Cook	Route:	I-94	M.P.:	39.7
Direction:	SB				
Description of Work	Unit	Quantity			
Remove Overhead Sign Structure - Span-Type II A	Foot	1.00			
Overhead Sign Structure Span Type II-A	Foot	82.00			
Remove & Reinstall Sign Panel	SQ FT	552.00			
Overhead Sign Structure Walkway (internal)	Foot	59.50			

Location No.:	1-08	State I.D. No.:	1S016U045L000.0-002 A2		
County:	Cook	Route:	US 45	M.P.:	0.9
Direction:					
Description of Work	Unit	Quantity			
Remove & Re-erect Overhead Sign Structure - Span	EACH	1.00			
Structural Steel Support Overhead Sign Structure	EACH	2.00			
Furnish & Install Saddle Shim Block	EACH	4.00			

Location No.:	1-09	State I.D. No.:	1S016S053L000.0-000 (TN-1) R3		
County:	Cook	Route:	IL 53	M.P.:	0.0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	59.00			

Location No.:	1-10	State I.D. No.:	1S016S053L000.0-001 (TN-2) R5		
County:	Cook	Route:	IL 53	M.P.:	0.0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	55.00			

Location No.:	1-11	State I.D. No.:	1S016S053L000.0-002 (TN-3) U1		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	59.00			

Location No.:	1-12	State I.D. No.:	1S016S053L000.0-003 (TN-4) U3		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	59.00			

Location No.:	1-13	State I.D. No.:	1C016S053L000.0-000 (CN-1) V1		
County:	Cook	Route:	IL 53	M.P.:	0.0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	22.50			

Location No.:	1-14	State I.D. No.:	1S016S053L000.0-004 (TN-5) V3		
County:	Cook	Route:	IL 53	M.P.:	0.9
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	59.00			

Location No.:	1-15	State I.D. No.:	1C016S053L000.0-001 (CN-2)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	20.50			

Location No.:	1-16	State I.D. No.:	1S016S053L000.0-005 (TN-6)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	59.00			

Location No.:	1-17	State I.D. No.:	1C016S053L000.0-002 (CN-3)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	24.00			

Location No.:	1-18	State I.D. No.:	1S016S053L000.0-006 (TN-1)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	58.00			

Location No.:	1-19	State I.D. No.:	1S016S053L000.0-007 (TN-2)		
County:	Cook	Route:	IL 53	M.P.:	0.0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	57.00			

Location No.:	1-20	State I.D. No.:	1S016S053L000.0-009 (TN-4) Z3		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	54.00			

Location No.:	1-21	State I.D. No.:	1C016S053L000.0-003 (CW-1)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	NB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	23.00			

Location No.:	1-22	State I.D. No.:	1C016S053R000.0-000 (CE-1)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	SB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	23.00			

Location No.:	1-23	State I.D. No.:	1C016S053R000.0-001 (CS-2)		
County:	Cook	Route:	IL 53	M.P.:	0
Direction:	SB				
Description of Work	Unit	Quantity			
Furnish & Install Handrail	Foot	24.00			

FILE NAME :	USER NAME :	DESIGNED -	REVISOR -
		CHECKED -	REVISIONS -
		DRAWN -	REVISIONS -
		CHECKED -	REVISIONS -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Ver 01 OVD SIN STR REPL11-30	COOK	3	26
ILLINOIS/FEH. AND PROJECT		CONTRACT NO. 46153	