

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	134(B&B-2)R-1	LAKE	137	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 62037

STAGE I

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USE IN EMBANKMENT ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION*	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU METER	CU METER	CUBIC METER	CUBIC METER	CUBIC METER	CUBIC METER
STA. 25+075.000 TO 25+084.530	—	—	—	—	1	-1
STA. 25+084.530 TO 25+093.530	42	—	—	—	1	-1
BRIDGE						
STA. 25+103.250 TO 25+112.250	39	—	—	—	4	-4
STA. 25+112.250 TO 25+125.000	—	—	—	—	4	-4
TOTAL	81	—	—	—	10	-10

STAGE II

EARTHWORK SCHEDULE						
LOCATION	EARTH EXCAVATION	ROCK EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USE IN EMBANKMENT ADJUSTED FOR SHRINKAGE	FURNISHED EXCAVATION*	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU METER	CU METER	CUBIC METER	CUBIC METER	CUBIC METER	CUBIC METER
STA. 25+075.000 TO 25+084.530	—	—	—	—	1	-1
STA. 25+084.530 TO 25+093.530	22	—	—	—	1	-1
BRIDGE						
STA. 25+103.250 TO 25+112.250	22	—	—	—	1	-1
STA. 25+112.250 TO 25+125.000	—	—	—	—	1	-1
TOTAL	44	—	—	—	4	-4

* INCLUDES 15% SHRINK

3117EARTHWORKSCHED.DGN

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL ROUTE 173 OVER WEST BOAT CHANNEL

EARTHWORK SCHEDULE

SCALE: NTS
DRAWN BY CLG
CHECKED BY JJD

DATE 3-8-10

