

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	IL 31	IL 31	IL 31	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY	IL 31	IL 31	IL 31
				1000-2A	@ OAK SIGNAL Y031-1F	INTER-CONNECT IL 56-OAK Y031-1F	@ OAK SIGNAL Y031-3D 100% NORTH AURORA					1000-2A	@ OAK SIGNAL Y031-1F	INTER-CONNECT IL 56-OAK Y031-1F	@ OAK SIGNAL Y031-3D 100% NORTH AURORA
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	143	143			
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	3				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	166	166			
60255500	MANHOLES TO BE ADJUSTED	EACH	3		3			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	127	127			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3		3			* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	731		551	180	
60266900	VALVE BOXES TO BE MOVED	EACH	6	6				* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	30		30		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2				* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	83		83		
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	14	14				* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	8		8		
60500050	REMOVING CATCH BASINS	EACH	10	10				* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	435		195	240	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3138	3138				* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	350		350		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				* 81400100	HANDHOLE	EACH	4		4		
67100100	MOBILIZATION	L SUM	1	1				* 81400200	HEAVY-DUTY HANDHOLE	EACH	4		4		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				* 81400300	DOUBLE HANDHOLE	EACH	2		2		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	55	45	10			* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	848		668	180	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1		1			* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1910	1910				* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	190	190				* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4080	4080				* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1102		1102		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1195	1195				* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1407		1407		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40	40				* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1630		1630		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	143	143				* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	905		905		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12225	12225				* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2249		2249		
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	900	900				* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	78		78		
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	52	52				* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1		1		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1803	1803				* 87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1		
72000100	SIGN PANEL - TYPE 1	SO FT	25.5		25.5			* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	190	190				* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4080	4080											
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1195	1195											
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40	40											

\* SPECIALITY ITEMS  
NP NON PARTICIPATING ITEMS  
# 100% COST TO THE VILLAGE OF NORTH AURORA

FILE NAME =	USER NAME = qureshiy	DESIGNED -	REVISED -
PLBT SCALE = 50,000' / IN.	PLBT DATE = 4/28/2010	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**IL 31 @ OAK STREET  
SUMMARY OF QUANTITIES**

F.A.U. RTE. 3887	SECTION A-R-N-1	COUNTY KANE	TOTAL SHEETS 77	SHEET NO. 4
CONTRACT NO. 62914				
SCALE: SHEET NO. 2 OF 3 SHEETS STA. TO STA. FED. ROAD DIST. NO. 1 ILL. FED. AID PROJECT				