

SUMMARY OF QUANTITIES					Paxton Ave.	River Oaks Dr.	Traffic Signals
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	1000-1A	J000-1A	Y031-1F
					80% Fed, 20% City	80% Fed, 20% State	80% Fed, 20% City
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	44	44		
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	66	66		
	20200100	EARTH EXCAVATION	CU YD	1041	760	281	
	20800150	TRENCH BACKFILL	CU YD	210	210		
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1216	1060	156	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	15	13	2	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	15	13	2	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15	13	2	
	25200110	SODDING, SALT TOLERANT	SQ YD	1216	1060	156	
	28000400	PERIMETER EROSION BARRIER	FOOT	833	833		
	28000510	INLET FILTERS	EACH	14	11	3	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2429	2247	182	
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1675	1675		
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3	3		
	40600300	AGGREGATE (PRIME COAT)	TON	142	142		
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	125	125		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	193	193		
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	500	500		
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	590	590		
	42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	427	245	182	
	42001300	PROTECTIVE COAT	SQ YD	1179	597	582	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2730	2548	182	
	42400800	DETECTABLE WARNINGS	SQ FT	24	24		
	44000100	PAVEMENT REMOVAL	SQ YD	800	800		
	44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	1734	1734		
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	1665	1665		
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	151	151		
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	604	604		
	44000300	CURB REMOVAL	FOOT	273	273		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2319	2039	280	
	44000600	SIDEWALK REMOVAL	SQ FT	1391	1391		
	44003100	MEDIAN REMOVAL	SQ FT	1762		1762	
	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	985		985	
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	120	120		
	44213200	SAW CUTS	FOOT	4356		4356	
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	957	957		
	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	62	62		
	542D0215	PIPE CULVERTS, CLASS D, TYPE 1 10"	FOOT	100	100		
	550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	15		15	
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	383	364	19	
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	190	190		
	55100500	STORM SEWER REMOVAL 12"	FOOT	56		56	
X	56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2	2		
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	2	2		
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4	4		
	60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	1	2	
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2		

* - INDICATES SPECIALTY ITEMS

revised 10-29-10

FILE NAME = 08329-quin-01 -001

USER NAME =	DESIGNED -- RW	REVISED -- 02-04-10
	CHECKED -- RW	REVISED --
PLOT SCALE =	DRAWN -- RG/PS	REVISED --
PLOT DATE = 01-25-10	CHECKED -- AG	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US ROUTE 6 (RIVER OAKS DRIVE) AT PAXTON AVENUE INTERSECTION IMPROVEMENT SUMMARY OF QUANTITIES		F.A.P. RTE. 351	SECTION 06-00139-00-CH	COUNTY COOK	TOTAL SHEETS 044	SHEET NO. 003
SCALE:	SHEET NO. 003 OF 044 SHEETS	STA.	TO STA.	CONTRACT NO. 63268		
		FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT HD-M-9003(258)		