

SUMMARY OF QUANTITIES

SPECIALTY ITEMS	PAY ITEM	ITEM DESCRIPTION	UNIT	CMAQ 80%	CONSTRUCTION		
				LOCAL 20%	TOTAL QUANTITY	SFTY-1B	Y002-1C
	67100100	MOBILIZATION	L SUM		1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM		1	1	
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM		1	1	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM		1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM		1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM		1	1	
	72000100	SIGN PANEL - TYPE 1	SQ FT		625		625
	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH		96		96
	72900210	METAL POST - TYPE B	EACH		190		190
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT		3,414	3414	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT		10,000	10000	
*	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT		391	391	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT		100	100	

TYLIN INTERNATIONAL

DESIGNED - SM	REVISED -
DRAWN - TG	REVISED -
CHECKED - DAJ	REVISED -
DATE - 10/2/09	REVISED -

**CITY OF DES PLAINES
STAGE 1 BIKE NETWORK**

SUMMARY OF QUANTITIES

F.A. RTE.	COUNTY	TOTAL SHEETS	SHEET NO.
09-00208-00-BT	COOK	51	4
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	
		CONTRACT NO 63359	