

21 SCHEDULE OF COMBINATION CONCRETE CURB AND GUTTER									
FROM STATION	TO STATION	OFFSET	CONCRETE CURB, TYPE B (FT) 60600605	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FT) 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED) (FT) 60605300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24 (MODIFIED) (FT) 60608524	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24 (FT) X6063600	REMARKS	PROTECTIVE COAT (SQ YD) 42001300
HUNT CLUB ROAD									
82+60.0	85+60.0	RT		322.0				-	966.0
82+65.0	82+65.0	LT				9.0		SPLITTER ISLAND NOSE	23.4
82+65.0	85+20.9	RT/LT			535.5			SPLITTER ISLAND	1606.5
84+30.7	85+50.0	LT		136.2				-	408.6
84+86.0	84+86.0	RT/LT	29.2					S. EDGE OF SIDEWALK	29.2
85+00.0	85+01.0	RT/LT	29.5					N. EDGE OF SIDEWALK	29.5
85+39.9	86+64.0	RT/LT					377.0	OUTSIDE OF TRUCK APRON	980.2
85+46.0	86+54.0	RT/LT	326.7					INSIDE OF TRUCK APRON	326.7
86+67.0	89+40.0	LT		281.8				-	845.4
86+83.0	89+35.0	RT/LT			535.5			SPLITTER ISLAND	1606.5
87+00.5	87+00.5	RT/LT	26.8					S. EDGE OF SIDEWALK	26.8
87+14.5	87+14.2	RT/LT	26.3					N. EDGE OF SIDEWALK	26.3
89+35.0	89+35.0	RT				9.2		SPLITTER ISLAND NOSE	23.9
108+99.0	111+88.5	RT		300.0				-	900.0
109+04.0	109+04.0	LT				9.4		SPLITTER ISLAND NOSE	24.4
109+04.0	111+76.1	RT/LT			556.6			SPLITTER ISLAND	1669.8
110+98.0	115+90.8	LT		519.3				-	1557.9
111+43.4	111+43.3	LT	14.3					S. EDGE OF SIDEWALK	14.3
111+56.8	111+57.0	RT/LT	14.2					N. EDGE OF SIDEWALK	14.2
111+95.1	112+99.1	RT/LT					314.2	OUTSIDE OF TRUCK APRON	816.9
112+02.9	112+90.9	RT/LT	263.9					INSIDE OF TRUCK APRON	263.9
112+90.0	116+87.1	RT		403.0				-	1209.0
113+18.1	115+85.8	RT/LT			549.4			SPLITTER ISLAND	1648.2
113+37.2	113+36.9	RT/LT	17.4					S. EDGE OF SIDEWALK	17.4
113+50.6	113+50.4	RT	17.4					N. EDGE OF SIDEWALK	17.4
115+85.8	115+85.8	RT				9.4		SPLITTER ISLAND NOSE	24.4
MILLBURN ROAD									
6+51.8	6+52.1	LT				9.2		SPLITTER ISLAND NOSE	23.9
6+51.8	9+17.0	RT/LT			562.0			SPLITTER ISLAND	1686.0
6+60.1	9+33.1	RT		283.6				-	850.8
8+42.4	9+50.2	LT		113.8				-	341.4
8+86.1	8+85.6	RT/LT	28.0					W. EDGE OF SIDEWALK	28.0
8+99.7	8+99.2	RT/LT	28.0					E. EDGE OF SIDEWALK	28.0
10+77.0	11+32.0	RT		59.5				-	178.5
10+77.0	11+32.0	LT		59.5				-	178.5
10+82.0	11+17.0	RT/LT			80.0			SPLITTER ISLAND	240.0
10+91.3	10+91.3	RT/LT	21.5					W. EDGE OF SIDEWALK	21.5
11+05.5	11+05.5	RT/LT	13.6					E. EDGE OF SIDEWALK	13.6
WADSWORTH ROAD									
10+44.3	11+43.5	RT		104.6				-	313.8
10+58.4	12+79.9	LT		232.5				-	697.5
10+73.0	12+74.9	RT/LT			419.8			SPLITTER ISLAND	1259.4
10+90.0	10+90.8	RT/LT	16.1					W. EDGE OF SIDEWALK	16.1
11+03.5	11+04.5	RT	16.1					E. EDGE OF SIDEWALK	16.1
12+74.9	12+75.0	RT				9.3		SPLITTER ISLAND NOSE	24.2
TOTAL			889	2,816	3,239	56	691		20,994

22 SCHEDULE OF WOVEN WIRE FENCE				
FROM STATION	TO STATION	OFFSET	WOVEN WIRE FENCE, 4' (FT) 66500105	WOVEN WIRE FENCE REMOVAL (FT) 66502300
HUNT CLUB ROAD				
81+75.0	82+50.0	RT	75	75
83+25.0	11+40.0 M	RT	272	330
92+50.0	99+00.0	LT	658	654
MILLBURN / HUNT CLUB ROAD				
5+12.0 M	89+60	LT	654	738
TOTAL			1,659	1,797

FILE NAME = s:\p1\1900--1999\1902\002\mcras\Plan Sheets\JL-ent-schedule.dgn



USER NAME = saoran	DESIGNED -	REVISED -
PLOT SCALE = 20,000' / IN.	DRAWN -	REVISED -
PLOT DATE = 4/1/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: AS SHOWN	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE. 2661	SECTION 02-00076-13-CH	COUNTY LAKE	TOTAL SHEETS 177	SHEET NO. 24
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 63457				