

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

NUMBER	STA		OFFSET		20004502 COMB C C&G REM & REPL (FOOT)	
	BEGIN	END	STAGE 1 (RT)	STAGE 2 (LT)	STAGE 1	STAGE 2
1	18+93	19+34	RT		41	
2	18+93	19+34		LT		41
3	19+47	19+51	RT		4	
4	19+47	19+51		LT		4
5	20+13	20+33	RT		20	
6	20+13	21+39		LT		126
7	21+33	21+79	RT		46	
8	21+61	22+13		LT		52
9	23+69	23+75	RT		6	
10	23+69	23+75		LT		6
11	24+94	25+94	RT		100	
12	26+09	26+26	RT		19	
13	29+29	29+35	RT		6	
14	29+29	29+35		LT		6
15	32+87	33+84	RT		97	
16	37+59	37+65	RT		6	
17	37+59	37+65		LT		6
18	38+07	38+13	RT		6	
19	38+07	38+13		LT		6
20	40+15	40+33	RT		18	
21	40+25	40+35		LT		10
22	43+64	43+86		LT		22
23	44+52	44+58	RT		6	
24	51+48	51+72	RT		24	
25	51+48	51+72		LT		24
26	52+03	52+09		LT		6
27	56+51	56+78	RT		27	
28	56+51	56+90		LT		39
29	60+90	61+26		LT		36
30	61+46	61+55	RT		9	
31	61+91	62+12	RT		21	
32	63+42	63+48	RT		6	
33	63+55	64+15		LT		60
34	63+98	64+23	RT		25	
35	65+23	65+77		LT		54
36	65+95	66+27	RT		32	
37	65+95	66+27		LT		32
38	66+88	67+12	RT		24	
39	66+88	67+09		LT		21
40	67+92	68+44	RT		52	
41	69+07	69+75		LT		68
42	69+96	70+10	RT		14	
43	69+96	70+27		LT		31
44	76+29	76+66		LT		37
45	78+06	78+23		LT		17
46	78+19	78+26	RT		7	
47	80+93	81+13	RT		20	
48	82+08	82+74		LT		66
49	83+91	84+24	RT		33	
50	83+91	84+24		LT		33
51	101+92	102+10	RT		18	
52	102+50	102+66	RT		16	
53	102+64	103+06		LT		42
54	104+38	104+47	RT		9	
55	106+16	106+33		LT		17
56	107+40	107+50	RT		10	
57	108+69	108+77	RT		8	
58	108+69	108+77		LT		8
59	110+18	110+31	RT		13	
60	110+20	110+33		LT		13
61	110+86	110+92		LT		6
62	112+32	112+51		LT		19
63	113+54	113+75		LT		21
64	113+69	113+75	RT		6	
65	121+32	121+49		LT		17
66	123+73	123+79		LT		6
TOTAL PER STAGE:					749	952
GRAND TOTAL:						1701

UTILITY STRUCTURES TO BE ADJUSTED

NUMBER	STA	OFFSET		60250200 CB ADJUST (EACH)		60255500 MAN ADJUST (EACH)		X6026050 SANITARY MANHOLE ADJ (EACH)		UTIL STR ADJUST BY OTHERS (EACH)	
		STAGE 1 (RT OR CL)	STAGE 2 (LT)	STAGE 1	STAGE 2	STAGE 1	STAGE 2	STAGE 1	STAGE 2	STAGE 1	STAGE 2
1	20+28	RT	LT	1	1						
2	21+50	RT		1							
3	26+24	RT		1							
4	40+30		LT		1						
5	43+76		LT		1						
6	58+31	RT								1	
7	58+51		LT						1		
8	59+45		LT						1		
9	60+95		LT						1		
10	61+00		LT			1					
11	63+97		LT, LT			1					
12	64+16	RT								1	
13	65+48		LT							1	
14	65+52		LT			1					
15	66+98		LT						1		
16	67+06		LT			1					
17	68+38	CL							1		
18	70+02	RT								1	
19	70+08	RT								1	
20	70+77		LT						1		
21	70+99	CL							1		
22	72+04		LT						1		
23	73+73	CL							1		
24	74+97		LT						1		
25	76+35	RT								1	
26	76+51	RT							1		
27	76+55		LT						1		
28	77+00	CL							1		
29	79+69	RT							1		
30	81+05				1						
31	82+35		LT			1					
32	82+37	RT								1	
33	82+47	RT							1		
34	83+92		LT				1				
35	83+94	CL							1		
36	84+01		LT				1				
37	84+18	RT				1					
38	100+67	RT								1	
39	100+77	RT								1	
40	101+56		LT						1		
41	102+77	RT							1		
42	102+85		LT				1				
43	102+88	RT								1	
44	103+00		LT				1				
45	104+43		LT				1				
46	104+76	CL							1		
47	106+22		LT						1		
48	107+39		LT						1		
49	107+68	CL							1		
50	107+80	RT								1	
51	108+71		LT				1				
52	108+74	RT	LT			1			1		
53	110+22	RT				1					
54	110+24		LT				1				
55	110+26		LT						1		
56	111+33	CL							1		
57	111+41		LT						1		
58	112+39	CL							1		
59	112+42	RT								1	
60	113+68	RT							1		
61	113+72	RT				1					
62	113+90		LT						1		
63	114+02	CL							1		
64	114+46		LT						1		
65	116+00		LT						1		
66	116+49	CL							1		
67	116+92	RT								1	
68	117+09		LT						1		
69	119+20	CL							1		
70	119+26		LT						1		
71	121+42		LT						1		
72	121+43		LT						1		
73	122+92	RT								1	
74	122+97	RT								1	
75	123+27		LT							1	
76	123+32		LT						1		
TOTAL PER STAGE:				8	14	1	24	16	2	14	0
GRAND TOTAL:					22		25		18		14

DRIVEWAY REMOVAL AND REPLACEMENT

PORTLAND CEMENT CONCRETE

NUMBER	STA		OFFSET		XX003435 PCC DRIVE REM & REPL (SQ YD)	
	BEGIN	END	STAGE 1 (RT)	STAGE 2 (LT)	STAGE 1	STAGE 2
1	78+08	78+25		LT		13
2	106+30	106+33		LT		1
3	121+32	121+35		LT		1
TOTAL PER STAGE:					0	15
GRAND TOTAL:						15

HOT MIX ASPHALT

NUMBER	STA		OFFSET		XX003829 DRIVE APPR REM & REPL (SQ YD)	
	BEGIN	END	STAGE 1 (RT)	STAGE 2 (LT)	STAGE 1	STAGE 2
1	24+94	25+94	RT		49	
2	32+87	33+84	RT		21	
3	51+51	51+72	RT		5	
4	65+95	66+27		LT		11
TOTAL PER STAGE:					75	11
GRAND TOTAL:						86

FILE NAME = 06-10\_Sch of Citys\_Washington  
PLOT DATE = 8/2/10



DESIGNED - BLP  
DRAWN - BLP  
CHECKED - KCV  
DATE - 08/02/10

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCALE: N.T.S.

WASHINGTON STREET - IL RTE 38 TO IL RTE 59  
SCHEDULE OF QUANTITIES - MISCELLANEOUS

F.A.U. RTE. 1397	SECTION 09-00076-00-RP	COUNTY DUPAGE	TOTAL SHEETS 61	SHEET NO. 10
CONTRACT NO. 63513				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(707)				