



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 27, 2010

SUBJECT: FAS 1233 (Dunham Road)
Project BHS-1233(106)
Section 06-00321-00-BR
McHenry County
Contract No. 63516
Item 74
November 5, 2010 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Schedule of Prices, pages 2, 3, 4, 5, 6 & 7.

Plans – Revised sheets 4, 9, 10, 11, 13, 14, 46 & 47. Added sheet 40A.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott Stitt
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by "P.E." in a smaller font.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

FAS 1233
 06-00321-00-BR
 MCHENRY

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63516

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 10/26/10
 RUN TIME - 183056

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
20201200	REM & DISP UNS MATL	CU YD	1,313.000 X				
20300100	CHANNEL EXCAVATION	CU YD	982.000 X				
20400800	FURNISHED EXCAVATION	CU YD	1,975.000 X				
20700220	POROUS GRAN EMBANK	CU YD	20.000 X				
20800150	TRENCH BACKFILL	CU YD	65.000 X				
21101625	TOPSOIL F & P 6	SQ YD	7,400.000 X				
25000210	SEEDING CL 2A	ACRE	0.500 X				
25000310	SEEDING CL 4	ACRE	1.000 X				
25000400	NITROGEN FERT NUTR	POUND	140.000 X				
25000500	PHOSPHORUS FERT NUTR	POUND	140.000 X				
25000600	POTASSIUM FERT NUTR	POUND	140.000 X				
25100635	HD EROS CONTR BLANKET	SQ YD	6,900.000 X				
28000200	EARTH EXC - EROS CONT	CU YD	30.000 X				
28000250	TEMP EROS CONTR SEED	POUND	920.000 X				
28000305	TEMP DITCH CHECKS	FOOT	100.000 X				

Revised 10-27-10

FAS 1233
 06-00321-00-BR
 MCHENRY

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63516

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 10/26/10
 RUN TIME - 183056

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
28000315	AGG DITCH CHECKS	TON	120.000 X	=	=	=	=
28000400	PERIMETER EROS BAR	FOOT	1,620.000 X	=	=	=	=
28000500	INLET & PIPE PROTECT	EACH	2.000 X	=	=	=	=
28000510	INLET FILTERS	EACH	4.000 X	=	=	=	=
28001000	AGGREGATE - EROS CONT	TON	15.000 X	=	=	=	=
28100105	STONE RIPRAP CL A3	SQ YD	15.000 X	=	=	=	=
28100107	STONE RIPRAP CL A4	SQ YD	857.000 X	=	=	=	=
28200200	FILTER FABRIC	SQ YD	872.000 X	=	=	=	=
28400100	GABIONS	CU YD	27.000 X	=	=	=	=
40201000	AGGREGATE-TEMP ACCESS	TON	70.000 X	=	=	=	=
40600100	BIT MATLS PR CT	GALLON	2,620.000 X	=	=	=	=
40600300	AGG PR CT	TON	10.000 X	=	=	=	=
40600400	MIX CR JTS FLANGEWYS	TON	1.000 X	=	=	=	=
40600625	LEV BIND MM N50	TON	20.000 X	=	=	=	=
40600982	HMA SURF REM BUTT JT	SQ YD	10.000 X	=	=	=	=

Revised 10-27-10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
40603080	HMA BC IL-19.0 N50	TON	280.000 X	=	=	=	=
40603310	HMA SC "C" N50	TON	180.000 X	=	=	=	=
42001300	PROTECTIVE COAT	SQ YD	50.000 X	=	=	=	=
42001430	BR APPR PVT CON (FLX)	SQ YD	890.000 X	=	=	=	=
44000100	PAVEMENT REM	SQ YD	1,960.000 X	=	=	=	=
44000158	HMA SURF REM 2 1/4	SQ YD	480.000 X	=	=	=	=
48203021	HMA SHOULDERS 6	SQ YD	810.000 X	=	=	=	=
50100100	REM EXIST STRUCT	EACH	1.000 X	=	=	=	=
50105220	PIPE CULVERT REMOV	FOOT	130.000 X	=	=	=	=
50200100	STRUCTURE EXCAVATION	CU YD	216.000 X	=	=	=	=
50300225	CONC STRUCT	CU YD	73.300 X	=	=	=	=
50300255	CONC SUP-STR	CU YD	276.800 X	=	=	=	=
50300260	BR DECK GROOVING	SQ YD	642.000 X	=	=	=	=
50300300	PROTECTIVE COAT	SQ YD	743.000 X	=	=	=	=
50401005	F & E P CON I-BM 48	FOOT	631.500 X	=	=	=	=

Revised 10-27-10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
50800205	REINF BARS, EPOXY CTD	POUND	67,280.000 X	=			
50800515	BAR SPLICERS	EACH	88.000 X	=			
51200958	FUR M S PILE 14X0.250	FOOT	1,079.000 X	=			
51202305	DRIVING PILES	FOOT	1,079.000 X	=			
51203200	TEST PILE MET SHELLS	EACH	2.000 X	=			
51500100	NAME PLATES	EACH	1.000 X	=			
542A0223	P CUL CL A 1 18	FOOT	78.000 X	=			
542A5479	P CUL CL A 1 EQRS 24	FOOT	26.000 X	=			
542C0223	P CUL CL C 1 18	FOOT	63.000 X	=			
54213657	PRC FLAR END SEC 12	EACH	3.000 X	=			
54213663	PRC FLAR END SEC 18	EACH	1.000 X	=			
54214509	PRC FL END S EQ RS 24	EACH	2.000 X	=			
550A0340	STORM SEW CL A 2 12	FOOT	123.000 X	=			
59100100	GEOCOMPOSITE WALL DR	SQ YD	114.000 X	=			
59300100	CONTR LOW-STRENG MATL	CU YD	20.000 X	=			

Revised 10-27-10

FAS 1233
 06-00321-00-BR
 MCHENRY

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - 63516

ECMS002 DTGECM03 ECMR003 PAGE 6
 RUN DATE - 10/26/10
 RUN TIME - 183056

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
60208210	CB TC T20F&G	EACH	4.000 X				
60240301	INLETS TB T8G	EACH	1.000 X				
60605000	COMB CC&G TB6.24	FOOT	175.000 X				
63000001	SPBGR TY A 6FT POSTS	FOOT	288.000 X				
63000003	SPBGR TY A 9FT POSTS	FOOT	25.000 X				
63100085	TRAF BAR TERM T6	EACH	4.000 X				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000 X				
63200310	GUARDRAIL REMOV	FOOT	273.000 X				
66503500	BARB W FENCE REM & RE	FOOT	790.000 X				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000 X				
67100100	MOBILIZATION	L SUM	1.000 X				
70102550	TR CONT-PROT TEMP DET	EACH	1.000 X				
70106800	CHANGEABLE MESSAGE SN	CAL MO	12.000 X				
72000100	SIGN PANEL T1	SQ FT	6.000 X				
72400100	REMOV SIN PAN ASSY TA	EACH	5.000 X				

Revised 10-27-10

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
72900100	METAL POST TY A	FOOT	8.000 X	=			
78000200	THPL PVT MK LINE 4	FOOT	1,590.000 X	=			
78000650	THPL PVT MK LINE 24	FOOT	13.000 X	=			
78008210	POLYUREA PM T1 LN 4	FOOT	360.000 X	=			
78200410	GUARDRAIL MKR TYPE A	EACH	16.000 X	=			
78201000	TERMINAL MARKER - DA	EACH	4.000 X	=			

TOTAL \$

- NOTE:
1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
 2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
 3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
 4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Revised 10-27-10