

NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE ACRS L25			NON-PART 80% STATE 20% VILLAGE	80% FED. 20% VILLAGE ACTE L22	NON-PART 100% VILLAGE
				0001 ROADWAY	0008 SN050-0250	0008 SN050-7201	0021 SIDEWALK	0031 ITEP	0043 WATER MAIN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	38	38	--	--	--	--	--
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16	--	--	--	--	--
20100500	TREE REMOVAL, ACRES	ACRE	0.36	0.36	--	--	--	--	--
20200200	ROCK EXCAVATION	CU YD	201	201	--	--	--	--	--
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6550	6550	--	--	--	--	--
20300100	CHANNEL EXCAVATION	CU YD	764	764	--	--	--	--	--
20400800	FURNISHED EXCAVATION	CU YD	6666	6666	--	--	--	--	--
20800150	TRENCH BACKFILL	CU YD	1727.4	893.3	--	--	--	--	834.1
* 25000100	SEEDING, CLASS 1	ACRE	0.51	0.51	--	--	--	--	--
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	155	155	--	--	--	--	--
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	155	155	--	--	--	--	--
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	155	155	--	--	--	--	--
* 25100115	MULCH, METHOD 2	ACRE	0.33	0.33	--	--	--	--	--
* 25100630	EROSION CONTROL BLANKET	SQ YD	939	939	--	--	--	--	--
* 25200110	SODDING, SALT TOLERANT	SQ YD	8707	8707	--	--	--	--	--
* 25200200	SUPPLEMENTAL WATERING	UNIT	392	392	--	--	--	--	--
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5090	5090	--	--	--	--	--
28000400	PERIMETER EROSION BARRIER	FOOT	1525	1525	--	--	--	--	--
28000500	INLET AND PIPE PROTECTION	EACH	14	14	--	--	--	--	--
28100107	STONE RIPRAP, CLASS A4	SQ YD	732	--	--	628	--	--	104
28200200	FILTER FABRIC	SQ YD	732	--	--	628	--	--	104
35100100	AGGREGATE BASE COURSE, TYPE A	TON	112	112	--	--	--	--	--
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	810	810	--	--	--	--	--
35501322	HOT-MIX ASPHALT BASE COURSE, 9 1/2"	SQ YD	240	240	--	--	--	--	--
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	143	143	--	--	--	--	--
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200	--	--	--	--	--
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	295	295	--	--	--	--	--
40600300	AGGREGATE (PRIME COAT)	TON	3.5	3.5	--	--	--	--	--
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.5	0.5	--	--	--	--	--
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	83	83	--	--	--	--	--
40600990	TEMPORARY RAMP	SQ YD	153	153	--	--	--	--	--
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	157	157	--	--	--	--	--
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	85	85	--	--	--	--	--
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	198	198	--	--	--	--	--
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	1977	1977	--	--	--	--	--
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	10120	10120	--	--	--	--	--

\* SPECIALTY ITEM

FILE NAME =  
0366547-SHT-SUM-QUANTS.DGN

USER NAME = ---  
PLOT SCALE = 1"=10'  
PLOT DATE = 08/10

DESIGNED - JKC  
DRAWN - ARR  
CHECKED - JKC  
DATE - 08/10

REVISED - ---  
REVISED - ---  
REVISED - ---  
REVISED - ---

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.S. RTE. 1279	SECTION 6R,B	COUNTY LASALLE	TOTAL SHEETS 190	SHEET NO. 3
CONTRACT NO. 66547				
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT				