

NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE ACRS L25			NON-PART 80% STATE 20% VILLAGE	80% FED. 20% VILLAGE ACTE L22	NON-PART 100% VILLAGE
				0001 ROADWAY	0008 SN050-0250	0008 SN050-7201	0021 SIDEWALK	0031 ITEP	0043 WATER MAIN
51203400	TEST PILE STEEL HP10X42	EACH	2	--	--	2	--	--	--
51500100	NAME PLATES	EACH	2	--	1	1	--	--	--
52100520	ANCHOR BOLTS, 1"	EACH	24	--	24	--	--	--	--
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	78	78	--	--	--	--	--
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	84	84	--	--	--	--	--
5421D018	PIPE CULVERTS, CLASS D, TYPE 1 18" (TEMPORARY)	FOOT	13	13	--	--	--	--	--
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4	--	--	--	--	--
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2	--	--	--	--	--
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4	--	--	--	--	--
54213678	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 33"	EACH	1	1	--	--	--	--	--
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	996	996	--	--	--	--	--
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	6	6	--	--	--	--	--
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	228	228	--	--	--	--	--
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	125	125	--	--	--	--	--
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	82	82	--	--	--	--	--
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	28	28	--	--	--	--	--
550A0440	STORM SEWERS, CLASS A, TYPE 2 33"	FOOT	312	312	--	--	--	--	--
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	453	453	--	--	--	--	--
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	31	31	--	--	--	--	--
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	134	134	--	--	--	--	--
550A2570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 27"	FOOT	97	97	--	--	--	--	--
550A2590	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 33"	FOOT	120	120	--	--	--	--	--
55100500	STORM SEWER REMOVAL 12"	FOOT	142	142	--	--	--	--	--
* 56100600	WATER MAIN 6"	FOOT	1958	186	--	--	--	--	1772
* 56100700	WATER MAIN 8"	FOOT	645	--	--	--	--	--	645
* 56200200	WATER SERVICE LINE 3/4"	FOOT	579	--	--	--	--	--	579
* 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	6	5	--	--	--	--	1
* 56400600	FIRE HYDRANTS	EACH	7	--	--	--	--	--	7
* 56500700	DOMESTIC WATER SERVICE BOXES TO BE REMOVED	EACH	5	2	--	--	--	--	3
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	344	--	--	344	--	--	--
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	1000	--	--	1000	--	--	--
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	291	--	235	56	--	--	--
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	271.0	30.4	--	--	--	--	240.6
20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	135	--	--	135	--	--	--
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	--	--	--	--	--
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7	7	--	--	--	--	--
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2	2	--	--	--	--	--

* SPECIALTY ITEM

FILE NAME =
0366547-SHT-SUM-QUANTS.DGN

USER NAME = ---
PLOT SCALE = 1"=10'
PLOT DATE = 08/10

DESIGNED - JKC
DRAWN - ARR
CHECKED - JKC
DATE - 08/10

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.S. RTE. 1279	SECTION 6R,B	COUNTY LASALLE	TOTAL SHEETS 190	SHEET NO. 5
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			CONTRACT NO. 66547	