

NO.	ITEM	UNIT	TOTAL QUANTITY	80% FEDERAL 20% STATE ACRS L25			NON-PART 80% STATE 20% VILLAGE	80% FED. 20% VILLAGE ACTE L22	NON-PART 100% VILLAGE
				0001 ROADWAY	0008 SN050-0250	0008 SN050-7201	0021 SIDEWALK	0031 ITEP	0043 WATER MAIN
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	--	--	--	--	--
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	3	3	--	--	--	--	--
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	--	--	--	--	--
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	15	15	--	--	--	--	--
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6	6	--	--	--	--	--
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	16	16	--	--	--	--	--
60240225	INLETS, TYPE B, TYPE 4 FRAME AND GRATE	EACH	1	1	--	--	--	--	--
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	--	--	--	--	--
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	--	--	--	--	--
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	--	--	--	--	--
60266910	VALVE BOXES TO BE REMOVED	EACH	7	5	--	--	--	--	2
60500040	REMOVING MANHOLES	EACH	2	2	--	--	--	--	--
60500050	REMOVING CATCH BASINS	EACH	5	5	--	--	--	--	--
60500060	REMOVING INLETS	EACH	9	9	--	--	--	--	--
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.9	3.9	--	--	--	--	--
60600605	CONCRETE CURB, TYPE B	FOOT	340	340	--	--	--	--	--
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5627	5627	--	--	--	--	--
60609600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (SPECIAL)	FOOT	88	88	--	--	--	--	--
60611815	COMBINATION CONCRETE CURB AND GUTTER, TYPE M (SPECIAL)	FOOT	1755	--	--	--	--	1755	--
60625800	ISLAND PAVEMENT (SPECIAL)	SQ YD	127	127	--	--	--	--	--
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	1	1	--	--	--	--	--
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	4	4	--	--	--	--	--
66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	2	2	--	--	--	--	--
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1438	1438	--	--	--	--	--
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1	--	--	--	--	--
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	--	--	--	--	--
66901000	BACKFILL PLUGS	CU YD	35	35	--	--	--	--	--
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	21	21	--	--	--	--	--
67100100	MOBILIZATION	L SUM	1	1	--	--	--	--	--
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	--	--	--	--	--
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	267	267	--	--	--	--	--
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	175.6	175.6	--	--	--	--	--
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9888	9888	--	--	--	--	--
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1743	1743	--	--	--	--	--
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	416	416	--	--	--	--	--
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	466	466	--	--	--	--	--

* SPECIALTY ITEM

FILE NAME =
D366547-SHT-SUM-QUANTS.DGN

USER NAME = ---
PLOT SCALE = 1"=10'
PLOT DATE = 08/10

DESIGNED - JKC
DRAWN - ARR
CHECKED - JKC
DATE - 08/10

REVISED - ---
REVISED - ---
REVISED - ---
REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____

F.A.S. RTE. 1279	SECTION 6R,B	COUNTY LASALLE	TOTAL SHEETS 190	SHEET NO. 6
CONTRACT NO. 66547				
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				