

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES IDOT FUNDING		CONSTRUCTION TYPE CODES LOCAL AGENCY FUNDING	
				0005	EX S.N. 032-0084 PR S.N. 032-2020 0010	0005	EX S.N. 032-0084 PR S.N. 032-2020 0010
				100% Village			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	206	206			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	38	38			
20200100	EARTH EXCAVATION	CU YD	569	300		269	
20300100	CHANNEL EXCAVATION	CU YD	40	40			
20400800	FURNISHED EXCAVATION	CU YD	2,423	1,031		1,392	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1,133		788		345
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	205		131		74
20800150	TRENCH BACKFILL	CU YD	14	14			
* 25000300	SEEDING, CLASS 3	ACRE	1.25	0.75		0.50	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	113	68		45	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	113	68		45	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	113	68		45	
* 25100115	MULCH, METHOD 2	ACRE	1.25	0.75		0.50	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	375	225		150	
28000305	TEMPORARY DITCH CHECKS	FOOT	180	110		70	
28000400	PERIMETER EROSION BARRIER	FOOT	598	467		131	
28000500	INLET AND PIPE PROTECTION	EACH	4	4			
28100105	STONE RIPRAP, CLASS A3	SQ YD	158	158			
28100107	STONE RIPRAP, CLASS A4	SQ YD	181		181		
28200200	FILTER FABRIC	SQ YD	339	158	181		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	288	288			
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	19	19			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	182	161		21	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	371	371			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	100	100			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	165	165			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	198	198			
44000100	PAVEMENT REMOVAL	SQ YD	103	103			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,273	2,273			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	81	81			
44000400	GUTTER REMOVAL	FOOT	18	18			
44004250	PAVED SHOULDER REMOVAL	SQ YD	17	17			
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	419	419			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	61	61			

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES IDOT FUNDING		CONSTRUCTION TYPE CODES LOCAL AGENCY FUNDING	
				0005	EX S.N. 032-0084 PR S.N. 032-2020 0010	0005	EX S.N. 032-0084 PR S.N. 032-2020 0010
				100% Village			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50105220	PIPE CULVERT REMOVAL	FOOT	118	118			
50200100	STRUCTURE EXCAVATION	CU YD	966		644		322
50800105	REINFORCEMENT BARS	POUND	21,840		17,300		4,540
51500100	NAME PLATES	EACH	1		1		
54003000	CONCRETE BOX CULVERTS	CU YD	90.0		74.1		15.9
54010906	PRECAST CONCRETE BOX CULVERT 9' X 6'	FOOT	238		144		94
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	143	143			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1			
54215550	METAL END SECTIONS 15"	EACH	6	6			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	68	68			
550A0320	STORM SEWERS, CLASS A, TYPE 2 8"	FOOT	50	50			
55100300	STORM SEWER REMOVAL 8"	FOOT	50	50			
55100700	STORM SEWER REMOVAL 15"	FOOT	15	15			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1	1			
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2			
63200310	GUARDRAIL REMOVAL	FOOT	247	247			
64200105	SHOULDER RUMBLE STRIPS	FOOT	900	900			
66500105	WOVEN WIRE FENCE, 4'	FOOT	100	100			
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	100	100			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	12	12			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1			
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2,147	2,147			
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	213	213			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11	11			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11			
X6660400	REMOVE RIGHT-OF-WAY MARKERS	EACH	2	2			
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22		22		
60608220	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.36	FOOT	75	75			

* SPECIALTY ITEM