

GENERAL NOTES

THE CONTRACTOR SHALL PROTECT ALL EXISTING TREES FROM DAMAGE DUE TO HIS OPERATIONS.

ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE TREE AND SHRUB PLANTING.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER SHOWN IN THE LIST OF STANDARDS OR THE COPY INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

ALL SOILS DISTURBED BY ANY CONSTRUCTION OPERATION SHALL BE LEFT ON, AND INCORPORATED WITHIN, THE PROJECT LIMITS AND EXISTING RIGHT-OF-WAY.

SUMMARY OF QUANTITIES				100% STATE	
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		0031	0031
		UNIT	TOTAL QUANTITY	FAI 55 QUANTITY	FAS 298 QUANTITY
67100100	MOBILIZATION	L SUM	1	0.7	0.3
A2000116	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	53		53
A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	37		37
A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	47		47
C2C00524	SHRUB, ARONIA MELANOCARPA (BLACK CHOKE BERRY), 2' HEIGHT, CONTAINER	EACH	606	606	
C2C008G3	SHRUB, RHUS AROMATICA (FRAGRANT SUMAC), CONTAINER GROWN, 3-GALLON	EACH	505	505	
C2C016G3	SHRUB, CORNUS RACEMOSA (GRAY DOGWOOD), CONTAINER GROWN, 3-GALLON	EACH	505	505	
C2012826	SHRUB, VIBURNUM TRILOBUM (AMERICAN CRANBERRY VIBURNUM), 30" HEIGHT, BALLED AND BURLAPPED	EACH	404	404	
D2C015G3	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), CONTAINER GROWN, 3-GALLON	EACH	505	505	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DISTRICT THREE

PREPARED BY: Don Brunil
ACTING DISTRICT STUDIES & PLANS ENGINEER

DATE: 08/12/10

EXAMINED BY: Herbert K. Dwyer
DISTRICT CONSTRUCTION ENGINEER

Tom J. Phillips
DISTRICT MATERIALS ENGINEER

Bruce A. Huslan
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = verdinem1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES & GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pw_work\pwwork\verdinem1\0180750\0366A22-sht-cover.dgn	PLOT SCALE = 50,0000' / IN.	DRAWN -	REVISED -			*	D3 TREE PLANTING 2011	LIVINGSTON	14	2	
	PLOT DATE = Jul 28, 2010 - 04:05:58 PM	CHECKED -	REVISED -			* FAI 55 & FAS 298 CONTRACT NO. 66A22					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					