

SCHEDULE - STAGE CONSTRUCTION TRAFFIC CONTROL SN 006-0009 & SN 006-0010					
LOCATION	TRAFFIC CONTROL AND PROTECTION STANDARD 701402 (SPECIAL)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	EACH	FOOT	FOOT	EACH	EACH
SN 006-0009	0.5	350	350	1	1
SN 006-0010	0.5		700		2
TOTAL	1	350	1050	1	3

SCHEDULE - PAVEMENT MARKING SN 006-0009 & SN 006-0010			
LOCATION	PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING LINE 4"	THERMOPLASTIC PAVEMENT MARKING LINE 6"
	SQ FT	FOOT	FOOT
SN 006-0009	388	988	125
SN 006-0010	388	988	125
TOTAL	776	1976	250