

# SCHEDULE OF QUANTITIES

## 28100107 STONE RIPRAP CLASS A4

LOCATION	AREA (SQ YD)
LT STA 48+00 - 48+92	120.0
RT STA 47+00 - 47+96	125.0
<b>TOTAL =</b>	<b>245.0</b>
<b>USE =</b>	<b>245.0</b>

## 28400100 GABIONS

LOCATION	VOLUME (CU YD)
LT STA 48+63.50 - 48+93.92	93.6
RT STA 46+98.83 - 47+29.25	93.7
<b>TOTAL =</b>	<b>187.3</b>
<b>USE =</b>	<b>188.0</b>

## 28200200 FILTER FABRIC

LOCATION	AREA (SQ YD)
LT STA 48+00.00 - 48+92.00 (RIPRAP APPLICATION)	120.0
RT STA 47+00.00 - 48+02.00 (RIPRAP APPLICATION)	125.0
LT STA 48+63.50 - 48+93.92 (GABION APPLICATION)	60.0
RT STA 46+98.83 - 47+29.25 (GABION APPLICATION)	60.0
<b>TOTAL =</b>	<b>365.0</b>
<b>USE =</b>	<b>365.0</b>

## 35100300 AGGREGATE BASE COURSE, TYPE A 4 INCH

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
47+00.00		49+00.00	200.0	25.0	555.6
<b>TOTAL =</b>					<b>555.6</b>
<b>USE =</b>					<b>560.0</b>

## 42000301 PCC PAVEMENT 8 INCH JOINTED

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
47+00.00		49+00.00	200.0	22.0	488.9
<b>TOTAL =</b>					<b>488.9</b>
<b>USE =</b>					<b>490.0</b>

## 42001300 PROTECTIVE COAT

STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)
47+00.00		49+00.00	200.0	22.0	488.9
<b>TOTAL =</b>					<b>488.9</b>
<b>USE =</b>					<b>490.0</b>

FILE NAME =	USER NAME = blockrt	DESIGNED - RTB	REVISED -
ci:\pw\work\p\dot\blockrt\d0128383\text.dgn		DRAWN - JRP	REVISED -
		CHECKED -	REVISED -
		DATE - 06/2008	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SHEET NO. OF SHEETS

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	Z-BR	VERMILION	49	13
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70016	