

SUMMARY OF QUANTITIES

F.A.P. RTE. 704	SECTION (LIN&TS-1)	COUNTY McLEAN	TOTAL SHEETS 497	SHEET NO. 11
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

		Funding		80% Federal	80% Federal	80% Federal	80% Federal	80% State	80% Federal	80% Federal	80% Federal	100% City	80% Federal	80% Federal	100% City	80% Federal	100% City	
		Breakout		20% State	20% State	20% State	10% State	20% City	10% State	13% State	20% City		20% State	20% City		20% State		
		URBAN																
		Construction																
		Code	TOTAL QTY	0004 ROADWAY	0040 RETAINING WALL S.N. 057-W001	0040 RETAINING WALL S.N. 057-W002	0021 SIDEWALK	0038 BIKE PATH	0021 ** SEE BELOW	0021 *** SEE BELOW	0021 **** SEE BELOW	0021 EMERGENCY PREEMPTION	0021 INTERCONNECT	0021 INTERCONNECT	0043 UTILITY ADJUSTMENTS	0021 COMBINATION LIGHTING	0021 COMBINATION LIGHTING	
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQM	3,303	3,303														
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	758	758														
M4402050	SIDEWALK REMOVAL	SQM	223	223														
M4402420	MEDIAN REMOVAL	SQM	190.4	190.4														
M4402030	GUTTER REMOVAL	METER	10	10														
M4405000	PAVED DITCH REMOVAL	METER	281	281														
* M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	1,209	1,209														
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQM	2,156	2,156														
M4812000	AGGREGATE SHOULDERS, TYPE B	MTON	24	24														
M4820600	HOT-MIX ASPHALT SHOULDERS 200MM	SQM	2,447	2,447														
M4830150	PORTLAND CEMENT CONCRETE SHOULDERS - 150MM	SQM	679	679														
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4														
M2075498	CONCRETE RETAINING WALL REMOVAL	METER	3	3														
M5010522	PIPE CULVERT REMOVAL	METER	345	345														
M5020100	STRUCTURE EXCAVATION	CUM	1,289		381	908												
M5030350	CONCRETE STRUCTURES	CUM	520	3	258	259												
M5030450	PROTECTIVE COAT	SQM	221		109	112												
M5080105	REINFORCEMENT BARS	KG	1,480	1,480														
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	41,630		21,190	20,340												
M2007128	HANDRAIL REMOVAL	METER	12	12														
M5090540	PIPE HANDRAIL	METER	93	93														
M5401010	PRECAST CONCRETE BOX CULVERT 900MM X 600MM	METER	0.6	0.6														
M5403000	CONCRETE BOX CULVERTS	CUM	7.6	7.6														

* SPECIALTY ITEMS

- ** VETERANS & MORRIS TRAFFIC SIGNALS
- *** VETERANS & GREENWOOD TRAFFIC SIGNALS
- **** MORRIS & SIX POINTS TRAFFIC SIGNALS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 6 OF 12
 DRAWN BY
 CHECKED BY
 DATE 05-27-09

SUMMARY OF QUANTITIES