

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	11N&TS-1	McLEAN	497	14
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

		Funding	80% Federal	80% Federal	80% Federal	80% Federal	80% State	80% Federal	80% Federal	80% Federal	100% City	80% Federal	80% Federal	100% City	80% Federal	100% City	
		Breakout	20% State	20% State	20% State	10% State	20% City	10% State	13% State	20% City		20% State	20% City		20% State		
		URBAN				10% City		10% City	7% City								
		Construction															
		Code	TOTAL QTY	0004 ROADWAY	0040 RETAINING WALL S.N.057-W001	0040 RETAINING WALL S.N.057-W002	0021 SIDEWALK	0038 BIKE PATH	0021 ** SEE BELOW	0021 *** SEE BELOW	0021 **** SEE BELOW	0021 EMERGENCY PREEMPTION	0021 INTERCONNECT	0021 INTERCONNECT	0043 UTILITY ADJUSTMENTS	0021 COMBINATION LIGHTING	0021 COMBINATION LIGHTING
*	M6300101	STEEL PLATE BEAM GUARD RAIL, TYPE A, 1.83M POSTS	METER	523.07	523.07												
	M6320030	GUARDRAIL REMOVAL	METER	394	394												
	M6640110	CHAIN LINK FENCE, 1.5 METER	METER	95.3	95.3												
	M6640200	NON-SPECIAL WASTE DISPOSAL	CU M	163	163												
	M7030100	SHORT-TERM PAVEMENT MARKING	METER	310	310												
	M7030210	TEMPORARY PAVEMENT MARKINGS- LETTERS AND SYMBOLS	SQ M	6.42	6.42												
	M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	9,200	9,200												
	M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	346	346												
*	M7200100	SIGN PANEL - TYPE 1	SQ M	13.77	13.77												
*	M7200200	SIGN PANEL - TYPE 2	SQ M	0.9	0.9												
*	M7800100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	19.1	19.1												
*	M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100MM	METER	2,276	2,276												
*	M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300MM	METER	156.3	156.3												
*	M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600MM	METER	41.4	41.4												
*	M7802100	POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS	SQ M	100.7	100.7												
*	M7802070	POLYUREA PAVEMENT MARKING TYPE II - LINE 100MM	METER	6,320	5,990			330									
*	M7802090	POLYUREA PAVEMENT MARKING TYPE II - LINE 300MM	METER	677.5	677.5												
*	M7802160	POLYUREA PAVEMENT MARKING TYPE II - LINE 600MM	METER	89.5	89.5												
	M7830100	PAVEMENT MARKING REMOVAL	SQ M	99	99												
*	M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	1,467					233	222	224		570	218			
*	M8100270	CONDUIT IN TRENCH, 65MM DIA., PVC	METER	98					20	52	26						
*	M812075	CONDUIT PUSHED, 75MM DIA., PVC SCHEDULE 80	METER	345													220 125
*	M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	62					44	4	14						
*	M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	132					14		18		100				
*	M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	137					51	51	35						
*	M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	213					107	37	69						
*	M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C NO. 6	METER	990													650 340

* SPECIALTY ITEMS
 ** VETERANS & MORRIS TRAFFIC SIGNALS
 *** VETERANS & GREENWOOD TRAFFIC SIGNALS
 **** MORRIS & SIX POINTS TRAFFIC SIGNALS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 SHEET 9 OF 12
 DATE 05-27-09
 DRAWN BY
 CHECKED BY

SUMMARY OF QUANTITIES