

**SCHEDULE OF QUANTITIES  
EARTHWORK**

F.A. RTE. 704	SECTION (1)N&TS-1	COUNTY McLEAN	TOTAL SHEETS 497	SHEET NO. 48
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

LOCATION	EARTH EXCAVATION (M2020010)					EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)					EMBANKMENT					BALANCE (+) WASTE (-) SHORTAGE FURNISHED EXCAVATION (M2040800)					
	CU. M.					CU. M.					CU. M.					CU. M.					
	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	STAGE 1	STAGE 2	STAGE 3	STAGE 4	STAGE 5	
VETERANS PARKWAY	1045	1377	425	115	0	784	1033	319	86	0	1605	1517	416	200	0	-821	-484	-97	-114	0	
MORRIS AVENUE	104	1324	840	3506	72	78	993	630	2630	54	0	2580	102	434	20	78	-1587	528	2196	34	
SIX POINTS ROAD, EAST OF MORRIS	1042	0	0	0	0	782	0	0	0	0	3231	0	0	0	0	-2450	0	0	0	0	
SIX POINTS ROAD, WEST OF MORRIS	0	2117	0	0	0	0	1588	0	0	0	0	10798	0	0	0	0	-9210	0	0	0	
SPRINGFIELD ROAD, S. OF SIX POINTS	2001	336	167	0	0	1501	252	125	0	0	4482	611	0	0	0	-2981	-359	125	0	0	
SPRINGFIELD ROAD, N. OF SIX POINTS	0	0	221	0	0	0	0	166	0	0	192	0	0	0	0	-192	0	166	0	0	
GREENWOOD AVE. EAST OF MORRIS	1642	1895	0	2114	0	1232	1421	0	1586	0	910	550	1036	1007	0	322	871	-1036	579	0	
GREENWOOD AVE. WEST OF MORRIS	0	15	0	0	141	0	11	0	0	106	813	22	0	0	0	-813	-11	0	0	106	
MCKAY STREET	0	12	0	0	0	0	9	0	0	0	0	121	0	0	0	0	-112	0	0	0	
SZAREK STREET	0	401	0	0	0	0	301	0	0	0	0	27	0	0	0	0	274	0	0	0	
RECREATION TRAIL, S. OF SIX POINTS	0	0	0	125	0	0	0	0	94	0	0	0	0	567	0	0	0	0	-473	0	
RECREATION TRAIL, N. OF SIX POINTS	421	0	0	0	0	316	0	0	0	0	24	0	0	0	0	292	0	0	0	0	
	6255	7477	1653	5860	213	4691	5608	1240	4395	160	11257	16226	1554	2208	20	-6566	-10618	-314	2187	140	
<b>TOTAL</b>																					
		21,458 CU. M.					16,094 CU. M.					31,265 CU. M.					15,171 CU. M.				

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION  SCHEDULE OF QUANTITIES   DRAWN BY MAC CHECKED BY PMH DATE 05-27-09
NAME	DATE	

**SCHEDULE OF QUANTITIES**