

**SCHEDULE OF QUANTITIES**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	LN&TS-1	McLEAN	497	55
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 70514				

<b>SUB-BASE GRANULAR MATERIAL, TYPE A 300 mm</b>		<b>M3110300</b>
LOCATION		SQ M
STA. 2+205.500 TO STA. 2+361.200, VETERANS PARKWAY		599
STA. 2+385.630 TO STA. 3+038.900, VETERANS PARKWAY		1409
STA. 2+397.880 TO STA. 2+418.000, VETERANS PARKWAY		24
STA. 2+405.349 TO STA. 2+466.630, VETERANS PARKWAY		55
STA. 2+473.300 TO STA. 3+050.400, VETERANS PARKWAY		1980
STA. 2+586.289 TO STA. 2+760.720, VETERANS PARKWAY		730
STA. 0+057.000 TO STA. 0+264.874, MORRIS AVE.		3939
STA. 0+297.960 TO STA. 0+606.000, MORRIS AVE.		6414
STA. 0+013.771 TO STA. 0+392.470, SIX POINTS ROAD		6731
STA. 0+427.548 TO STA. 0+673.930, SIX POINTS ROAD		2380
STA. 0+865.521 TO STA. 1+088.342, SPRINGFIELD RD.		2271
STA. 16+574.971 TO STA. 16+662.681, SPRINGFLD RD.		899
STA. 6+989.437 TO STA. 7+128.629, GREENWOOD AVE.		1665
STA. 10+007.765 TO STA. 10+776.425, GREENWOOD AVE.		8398
STA. 5+016.787 TO 5+050.512, MCKAY STREET		415
STA. 3+937.700 TO 3+984.143, SZAREK STREET		510
	<b>TOTAL</b>	<b>38389</b>

<b>AGGREGATE BASE COURSE, TYPE B 150MM</b>		<b>M3511150</b>
LOCATION		SQ M
STA. 15+007.074 TO STA. 15+115.503, RECREATION TRAIL		362
STA. 16+014.954 TO STA. 16+087.795, RECREATION TRAIL		240
STA. 16+225.366 TO STA. 16+238.730, RECREATION TRAIL		44
STA. 0+022.0 TO STA. 0+130.0, RT. MORRIS AVE. (TEMP.)	STAGE 1	185
STA. 10+216.2 TO STA. 10+248.5, RT. GRNWD. AVE. (TEMP.)	STAGE 1	181
STA. 10+405.8 TO STA. 10+897.7, RT. GRNWD. AVE. (TEMP.)	STAGE 1	2120
STA. 0+418.6 TO STA. 0+437.1, LT. MORRIS AVE. (TEMP.)	STAGE 2	112
STA. 0+523.6 TO STA. 0+649.0, RT. MORRIS AVE. (TEMP.)	STAGE 2	208
STA. 9+994.8 TO STA. 10+216.2, RT. GRNWD. AVE. (TEMP.)	STAGE 2	1430
STA. 0+022.0 TO STA. 0+117.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	121
STA. 0+150.0 TO STA. 0+226.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	271
STA. 0+511.4 TO STA. 0+553.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	110
STA. 0+588.1 TO STA. 0+657.6, LT. MORRIS AVE. (TEMP.)	STAGE 3	327
	<b>TOTAL</b>	<b>6709</b>

<b>HOT-MIX ASPHALT BASE COURSE, 280MM</b>		<b>M3550590</b>
LOCATION		SQ M
STA. 2+205.500 TO STA. 2+361.200, VETERANS PARKWAY		360
STA. 2+385.630 TO STA. 2+540.500, VETERANS PARKWAY		479
STA. 2+401.740 TO STA. 2+418.000, VETERANS PARKWAY		9
STA. 2+473.300 TO STA. 3+050.400, VETERANS PARKWAY		1874
STA. 2+586.289 TO STA. 2+760.600, VETERANS PARKWAY		716
STA. 2+706.959 TO STA. 2+736.824, VETERANS PARKWAY		128
	<b>TOTAL</b>	<b>3566</b>

<b>AGGREGATE SURFACE COURSE, TYPE B</b>		<b>M4021010</b>	
LOCATION		OFFSET	M TON
10+088.535 TO 10+168.872, GREENWOOD AVE.	RT	200	
	<b>TOTAL</b>	<b>200</b>	

<b>TEMPORARY RAMP</b>		<b>M4080990</b>
STATION	LOCATIO	SQ M
2+205.5 TO 2+207.02, VETERANS PKWY	N. BOUND	11
2+205.5 TO 2+207.02, VETERANS PKWY	S. BOUND	12
2+304.5 TO 2+401.2, VETERANS PKWY AT MORRIS	N. BOUND	147
2+332.0 TO 2+398.0, VETERANS PKWY AT MORRIS	S. BOUND	100
0+873.93 TO 0+875.45, SIX POINTS RD		7
2+707.0 TO 2+736.0 VETERANS PKWY AT GREENW.		44
3+048.88 TO 3+050.4 VETERANS PKWY	N. BOUND	11
3+048.88 TO 3+050.4 VETERANS PKWY	S. BOUND	11
	<b>TOTAL</b>	<b>343</b>

<b>LEVELING BINDER (MACHINE METHOD), N30</b>		<b>M4062115</b>
LOCATION		M TON
STA. 16+087.795 TO STA. 16+225.366, RECREATION TRAIL		13
	<b>TOTAL</b>	<b>13</b>

<b>HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30</b>		<b>M4062115</b>
LOCATION		M TON
STA. 15+007.074 TO STA. 15+115.503, RECREATION TRAIL		60
STA. 16+014.954 TO STA. 16+238.730, RECREATION TRAIL		126
	<b>TOTAL</b>	<b>186</b>

<b>POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N90</b>		<b>M4063240</b>
LOCATION		M TON
STA. 2+205.500 TO STA. 2+361.200, VETERANS PARKWAY		50
STA. 2+385.630 TO STA. 2+540.500, VETERANS PARKWAY		66
STA. 2+401.740 TO STA. 2+418.000, VETERANS PARKWAY		1
STA. 2+473.300 TO STA. 3+050.400, VETERANS PARKWAY		260
STA. 2+586.289 TO STA. 2+760.600, VETERANS PARKWAY		99
STA. 2+706.959 TO STA. 2+736.824, VETERANS PARKWAY		18
	<b>TOTAL</b>	<b>494</b>

<b>POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90</b>		<b>M4063570</b>
LOCATION		M TON
STA. 2+205.500 TO STA. 3+050.400, VETERANS PARKWAY		1496
	<b>TOTAL</b>	<b>1496</b>

<b>TEMPORARY PAVEMENT</b>		<b>PCC OPTION</b>	<b>HMA OPTION</b>	<b>MX030199</b>
		<b>THICKNESS</b>	<b>THICKNESS</b>	
		(MM)	(MM)	SQM
STA. 0+022.0 TO STA. 0+130.0, RT. MORRIS AVE. (TEMP.)	STAGE 1	203	254	185
STA. 10+216.2 TO STA. 10+248.5, RT. GRNWD. AVE. (TEMP.)	STAGE 1	178	203	187
STA. 10+405.8 TO STA. 10+897.7, RT. GRNWD. AVE. (TEMP.)	STAGE 1	178	203	2123
STA. 0+418.6 TO STA. 0+437.1, LT. MORRIS AVE. (TEMP.)	STAGE 2	203	330	113
STA. 0+523.6 TO STA. 0+649.0, RT. MORRIS AVE. (TEMP.)	STAGE 2	203	330	206
STA. 9+994.8 TO STA. 10+216.2, RT. GRNWD. AVE. (TEMP.)	STAGE 2	178	203	1426
STA. 0+022.0 TO STA. 0+117.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	203	254	120
STA. 0+150.0 TO STA. 0+226.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	203	254	271
STA. 0+511.4 TO STA. 0+553.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	203	330	109
STA. 0+588.1 TO STA. 0+657.6, LT. MORRIS AVE. (TEMP.)	STAGE 3	203	330	327
			<b>TOTAL</b>	<b>5087</b>

<b>BITUMINOUS MATERIALS (PRIME COAT)</b>		<b>M408100</b>
LOCATION		LITER
STA. 0+022.0 TO STA. 0+130.0, RT. MORRIS AVE. (TEMP.)	STAGE 1	380
STA. 10+216.2 TO STA. 10+248.5, RT. GRNWD. AVE. (TEMP.)	STAGE 1	371
STA. 10+405.8 TO STA. 10+897.7, RT. GRNWD. AVE. (TEMP.)	STAGE 1	4348
STA. 0+418.6 TO STA. 0+437.1, LT. MORRIS AVE. (TEMP.)	STAGE 2	230
STA. 0+523.6 TO STA. 0+649.0, RT. MORRIS AVE. (TEMP.)	STAGE 2	422
STA. 9+994.8 TO STA. 10+216.2, RT. GRNWD. AVE. (TEMP.)	STAGE 2	2932
STA. 0+022.0 TO STA. 0+117.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	248
STA. 0+150.0 TO STA. 0+226.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	555
STA. 0+511.4 TO STA. 0+553.8, LT. MORRIS AVE. (TEMP.)	STAGE 3	225
STA. 0+588.1 TO STA. 0+657.6, LT. MORRIS AVE. (TEMP.)	STAGE 3	670
STA. 2+205.500 TO STA. 2+361.200, VETERANS PARKWAY		864
STA. 2+385.630 TO STA. 2+540.500, VETERANS PARKWAY		1150
STA. 2+401.740 TO STA. 2+418.000, VETERANS PARKWAY		22
STA. 2+473.300 TO STA. 3+050.400, VETERANS PARKWAY		4498
STA. 2+586.289 TO STA. 2+760.600, VETERANS PARKWAY		1718
STA. 2+706.959 TO STA. 2+736.824, VETERANS PARKWAY		307
STA. 2+205.500 TO STA. 3+050.400, VETERANS PARKWAY		6909
STA. 15+007.074 TO STA. 15+115.503, RECREATION TRAIL		615
STA. 16+014.954 TO STA. 16+087.795, RECREATION TRAIL		408
STA. 16+087.795 TO STA. 16+225.366, RECREATION TRAIL		145
STA. 16+225.366 TO STA. 16+238.730, RECREATION TRAIL		75
	<b>TOTAL</b>	<b>27090</b>

<b>PORTLAND CEMENT CONCRETE PAVEMENT 210 mm (JOINTED)</b>		<b>M4202215</b>
LOCATION		SQ M
STA. 0+865.521 TO STA. 1+088.342, SPRINGFIELD ROAD		2178
STA. 16+574.971 TO STA. 16+622.681, SPRINGFIELD ROAD		803
STA. 6+989.437 TO STA. 7+165.768, GREENWOOD AVE.		1595
STA. 5+016.787 TO STA. 5+049.035, MCKAY STREET		342
STA. 3+937.700 TO STA. 3+984.143, SZAREK STREET		430
	<b>TOTAL</b>	<b>5348</b>

<b>PORTLAND CEMENT CONCRETE PAVEMENT 220 mm (JOINTED)</b>		<b>M4202225</b>
LOCATION		SQ M
STA. 0+057.000 TO STA. 0+264.874, MORRIS AVE.		3575
STA. 0+297.960 TO STA. 0+606.000, MORRIS AVE.		5770
STA. 10+008.551 TO STA. 10+775.334, GREENWOOD AVE.		7788
	<b>TOTAL</b>	<b>17133</b>

<b>REVISIONS</b>		ILLINOIS DEPARTMENT OF TRANSPORTATION  SCHEDULE OF QUANTITIES  DRAWN BY DATE 05-27-09 CHECKED BY
NAME	DATE	

**SCHEDULE OF QUANTITIES**