

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(LIN&TS-1	McLEAN	497	56A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

PAVED DITCH REMOVAL		M4405000
STATION	OFFSET	METER
0+889.4 TO 0+879.0, SPRINGFIELD ROAD	LT	38.1
0+885.9 TO 0+925.2, SPRINGFIELD ROAD	LT	9.8
6+893 TO 7+061.7, GREENWOOD AVE.	RT \ LT	69.3
7+019.7 TO 7+037.0, GREENWOOD AVE.	LT	20.1
7+131.6 TO 7+161.2, GREENWOOD AVE.	LT	35.9
10+415.3 TO 10+519.3, GREENWOOD AVE.	LT	107.5
TOTAL		280.5

STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A		M4430090
STATION	LANE	METER
2+205.500 TO 2+381.200, VETERANS PKWY	N. BOUND	158
2+331.904 TO 2+381.200, VETERANS PKWY	S. BOUND	29
2+381.200, 3.100 M RT. TO 13.270 M RT.	INTERSEC	10
2+385.6 TO 2+437.5, VETERANS PKWY	N. BOUND	52
2+385.6, 5.8 M RT TO 16.0 M RT	INTERSEC	10
2+385.6 TO 2+540.5	S. BOUND	155
2+473.3 TO 3.050.4	S. BOUND	577
2+588.3 TO 2+780.7	N. BOUND	174
2+712.2 TO 2+734.8	MEDIAN	45
TOTAL		1209

AGGREGATE SHOULDERS, TYPE A 150 MM		M4810150
LOCATION	OFFSET	SQ M
STA. 0+887.0 TO STA. 0+892.2, SPRINGFIELD ROAD	LT	30
STA. 0+887.0 TO STA. 0+984.4, SPRINGFIELD ROAD	RT	141
STA. 0+898.0 TO STA. 0+930.2, SPRINGFIELD ROAD	LT	38
STA. 0+948.6 TO STA. 1+048.7, SPRINGFIELD ROAD	LT	120
STA. 0+992.8 TO STA. 1+050.3, SPRINGFIELD ROAD	RT	69
STA. 1+060.4 TO STA. 1+078.1, SPRINGFIELD ROAD	RT	18
STA. 1+053.7 TO STA. 1+078.6, SPRINGFIELD ROAD	LT	28
STA. 6+989.437 TO STA. 7+154.5, GREENWOOD AVE.	RT	198
STA. 6+989.437 TO STA. 7+107.9, GREENWOOD AVE.	LT	142
STA. 7+117.1 TO STA. 7+141.3, GREENWOOD AVE.	LT	29
STA. 7+149.3 TO STA. 7+158.0, GREENWOOD AVE.	LT	8
STA. 10+074.765 TO STA. 10+297.400, GREENWOOD AVE.	RT	320
STA. 10+185.028 TO STA. 10+208.828, GREENWOOD AVE.	LT	30
STA. 10+216.800 TO STA. 10+246.800, GREENWOOD AVE.	RT	34
STA. 10+417.900 TO STA. 10+707.05, GREENWOOD AVE.	RT	249
STA. 10+330.4 TO STA. 10+428.700, GREENWOOD AVE.	LT	180
STA. 10+418.0 TO STA. 10+509.3, GREENWOOD AVE.	RT	110
STA. 10+485.1 TO STA. 10+730.7, GREENWOOD AVE.	LT	295
STA. 10+516.7 TO STA. 10+519.0, GREENWOOD AVE.	RT	3
STA. 10+531.7 TO STA. 10+537.7, GREENWOOD AVE.	RT	7
STA. 10+544.8 TO STA. 10+548.4, GREENWOOD AVE.	RT	4
STA. 10+572.1 TO STA. 10+585.8, GREENWOOD AVE.	RT	28
STA. 10+615.3 TO STA. 10+631.4, GREENWOOD AVE.	RT	20
STA. 10+640.5 TO STA. 10+649.4, GREENWOOD AVE.	RT	11
STA. 10+680.3 TO STA. 10+687.4, GREENWOOD AVE.	RT	45
STA. 10+704.6 TO STA. 10.723.6, GREENWOOD AVE.	RT	19
TOTAL		2156

AGGREGATE SHOULDERS, TYPE B		M4812000
LOCATION		MTON
STA. 2+205.500 TO STA. 2+331.500 VETERANS PARKWAY		6
STA. 2+205.500 TO STA. 2+304.600 VETERANS PARKWAY		5
STA. 2+785.200 TO STA. 3+050.400 VETERANS PARKWAY		13
TOTAL		24

HOT-MIX ASPHALT SHOULDERS 200MM		M4820800
LOCATION	OFFSET	SQ M
STA. 2+416.020 TO STA. 2+646.010, VETERANS PARKWAY	LT	558
STA. 2+646.010 TO STA. 2+672.285, VETERANS PARKWAY	LT (GORE)	80
STA. 2+667.200 TO STA. 3+053.520, VETERANS PARKWY	LT	1125
STA. 2+401.250 TO STA. 2+588.289, VETERANS PARKWAY	RT	447
STA. 2+588.289 TO STA. 2+698.143, VETERANS PARKWAY	RT	157
STA. 2+739.500 TO STA. 2+750.700, VETERANS PARKWAY	RT	22
STA. 0+673.930 TO STA. 0+693.169, SIX POINTS ROAD	LT	60
TOTAL		2447

PORTLAND CEMENT CONCRETE SHOULDERS, 150 MM		M4830150
LOCATION	OFFSET	SQ M
STA. 0+530.000 TO STA. 0+673.930, SIX POINTS ROAD	RT	341
STA. 0+545.000 TO STA. 0+673.930, SIX POINTS ROAD	LT	338
TOTAL		679

CONCRETE HEADWALL REMOVAL		50104400
STATION	OFFSET	EACH
2+445 VETERANS PARKWAY	RT	1
0+261 SIX POINTS ROAD	RT	1
0+281 SIX POINTS ROAD	LT	1
0+973 SPRINGFIELD ROAD	22M RT	1
TOTAL		4

CONCRETE RETAINING WALL REMOVAL		M5010480
STATION	OFFSET	METER
0+354.7, SIX POINTS ROAD	LT	3.3
TOTAL		3.3

PIPE CULVERT REMOVAL		M5010522
STATION	OFFSET	METER
0+221 TO 0+228 MORRIS AVE.	RT	5
0+483 TO 0+498 MORRIS AVE.	RT	15
0+538 TO 0+557 MORRIS AVE.	RT	19
0+584 TO 0+596 MORRIS AVE.	RT	12
0+004 TO 0+017 SIX POINTS RD.	LT	13
0+016 TO 0+023 SIX POINTS RD.	RT	7
0+031 TO 0+038 SIX POINTS RD.	LT	7
0+044 TO 0+053 SIX POINTS RD.	RT	9
0+044 TO 0+051 SIX POINTS RD.	LT	7
0+078 TO 0+085 SIX POINTS RD.	LT	7
0+078 TO 0+085 SIX POINTS RD.	RT	7
0+108 TO 0+115 SIX POINTS RD.	LT	7
0+139 TO 0+148 SIX POINTS RD.	LT	7
0+168 TO 0+174 SIX POINTS RD.	LT	6
0+191 TO 0+195 SIX POINTS RD.	LT	4
0+197 TO 0+211 SIX POINTS RD.	LT	14
0+346 TO 0+381 SIX POINTS RD.	LT	35
0+879 TO 0+886 SPRINGFIELD RD.	LT	7
0+925 TO 0+949 SPRINGFIELD RD.	LT \ RT	26
10+005 TO 10+025, GREENWOOD AVE.	RT	20
10+207 TO 10+217 GREENWOOD AVE.	RT	9
10+409 TO 10+430 GREENWOOD AVE.	RT	21
10+508 TO 10+525 GREENWOOD AVE.	RT	19
10+808 TO 10+814 GREENWOOD AVE.	RT	8
10+630 TO 10+641 GREENWOOD AVE.	RT	11
10+647 TO 10+661 GREENWOOD AVE.	RT	14
10+697 TO 10+707 GREENWOOD AVE.	RT	10
2+352 TO 2+371 VETERANS PARKWAY	RT	19
TOTAL		345

HANDRAIL REMOVAL		M5090040
STATION	OFFSET	METER
0+222 MORRIS AVE. (AT STEPS)	RT	6
0+225 MORRIS AVE. (AT STEPS)	RT	6
TOTAL		12

PIPE HANDRAIL		M5090540
STATION	OFFSET	METER
0+146.0 TO 0+182.0 MORRIS	LT	36
0+193.0 TO 0+250.0 MORRIS	RT	57
TOTAL		93

DUCTILE IRON WATER MAIN 200MM		M5810420
LOCATION		METER
STA. 0+112.130, 4.9 M LT TO STA. 0+116.048, 59.800 M RT	SIX POINT	67
TOTAL		67

TAPPING VALVES AND SLEEVES 200MM		M5611215
LOCATION	OFFSET	EACH
STA. 0+112.130, SIX POINTS ROAD	4.9M LT	1
TOTAL		1

OUTLET SPECIAL		X0324058
STATION	OFFSET	EACH
2+456.681, VETERANS PARKWAY	RT	1
11+367.125, VETERANS PARKWAY	LT	1
TOTAL		2

CURB AND GUTTER OUTLET, SPECIAL		X0932150
STATION		EACH
2+308.042, VETERANS PARKWAY	RT	1
2+350.383, VETERANS PARKWAY	LT	1
2+414.220, VETERANS PARKWAY	LT	1
2+416.007, VETERANS PARKWAY	LT	1
2+486.600, VETERANS PARKWAY	RT	1
2+669.800, VETERANS PARKWAY	RT	1
1+078.577, SPRINGFIELD ROAD	LT	1
1+078.117, SPRINGFIELD ROAD	RT	1
16+411.487, SPRINGFIELD ROAD	LT	1
7+156.215, GREENWOOD AVE.	LT	1
10+022.985, GREENWOOD AVE.	LT	1
10+074.765, GREENWOOD AVE.	LT	1
10+428.700, GREENWOOD AVE.	LT	1
10+478.900, GREENWOOD AVE.	LT	1
10+730.700, GREENWOOD AVE.	LT	1
10+730.754, GREENWOOD AVE.	RT	1
TOTAL		18

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

DRAWN BY MAC
CHECKED BY PMH
DATE 05-27-09

SCHEDULE OF QUANTITIES