

SCHEDULE OF QUANTITIES

POLYUREA PAVEMENT MARKING, TYPE II
SIX POINTS ROAD, SPRINGFIELD ROAD, GREENWOOD AVE.

F.A. RTE. 704	SECTION (1)N&TS-1	COUNTY McLEAN	TOTAL SHEETS 497	SHEET NO. 60
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 70514				

STATION TO STATION	LETTERS AND SYMBOLS		LINE										
	LEFT OR RIGH ARROW	COMB. LEFT (RIGHT) AND THROUGH ARRO	LANE LINE SOLID YELLOW 100 mm (DOUBLE)	LANE LINE SKIP DASH WHITE 100 mm	LANE LINE DOTTED WHITE 100 mm	EDGE LINE SOLID YELLOW 100 mm	EDGE LINE SOLID WHITE 100 mm	LANE LINE SOLID WHITE 100 mm	CROSSWALK SOLID WHITE 150 mm	CROSSWALK SOLID WHITE 300 mm	STOP BAR SOLID WHITE 600 mm	MEDIAN SOLID YELLOW 100 mm	MEDIAN SOLID YELLOW 300 mm
	SQ M	SQ M	M	M	M	M	M	M	M	M	M	M	M
SIX POINTS ROAD													
0+013.7 TO 0+100.0			172.6										
0+013.7 TO 0+066.8								53.1					
0+022.0 TO 0+075.0					13.3								
0+020.0	1.47												
0+066.8 TO 0+387.3													
0+075.0 TO 0+391						80.2							
0+111.9 TO 0+118.0												6.1	
0+124.0 TO 0+191.9			135.8										
0+198.3 TO 0+204.2												3.9	
0+216.3 TO 0+285.9												282.4	37.8
0+307.0													
0+307.0 TO 0+353.5								46.5					
0+307.0 TO 0+355.2			96.4										
0+312.8	1.47												
0+318.1	2.94												
0+333.2	1.47												
0+338.8	2.94												
0+353.5 TO 0+392.2							9.7						
0+353.5	1.47												
0+355.2 TO 0+392.2												74	13.6
0+361.9	2.94												
0+385.0	2.94												
0+390.8												12.0	
0+440.0												13.8	
0+440.0 TO 0+521.0								162.0					
0+445.8	1.47	2.42											
0+464.6	1.47	2.42											
0+483.4	1.47	2.42											
0+502.2	1.47	2.42											
0+521.0	1.47	2.42											
0+521.0 TO 0+673.9													
0+521.0 TO 0+673.9							152.9	152.9					
SPRINGFIELD ROAD													
0+865.5 TO 1+084.2			437.4										
0+865.5 TO 1+078.0													
0+998.6 TO 1+039.1					10.1								
1+039.1 TO 1+084.2													
1+039.1	2.94												
1+058.8	2.94												
1+078.4	2.94												
1+084.2												8.8	
GREENWOOD AVENUE													
6+989.4 TO 7+160.4			342.0										
6+989.4 TO 7+156.5													
7+160.4													
7+161.6													
7+164.0													
7+161.6 TO 7+164.0													
10+080.0 TO 10+304.0			448.0										
10+304.0													
10+308.3													
10+320.0, 14.0M LT TO 38.3M LT			48.6										
10+322.6, 14.0M LT	1.47												
10+322.6, 33.9M LT	1.47												
10+325.2, 14.0M LT TO 38.3M LT													
10+330.9, 14.0M LT	1.47												
10+330.9, 33.9M LT	1.47												
10+320.0 TO 10+336.4, 38.3M LT													
10+349.0													
10+349.0 TO 10+397.0			96.0										
TOTAL	39.69	12.1	1776.8	159.2	33.1	152.9	940.2	306.7	27.1	26.4	85.2	356.4	51.4

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES DRAWN BY MAC CHECKED BY PMH DATE 05-27-09
NAME	DATE	

SCHEDULE OF QUANTITIES