

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
704	(1)N & TS-1	McLean	497	269
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 70514

### SCHEDULE OF QUANTITIES LIGHTING ITEMS

CODE NO.	ITEM	UNIT	TOTAL QTY	VETERANS PKWY & MORRIS AVE	VETERANS PKWY & GREENWOOD AVE	MORRIS AVE & SIX POINTS RD
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO CELL CONTROL 250 WATT	EACH	10	4	3	3
	CONDUIT PUSHED, 75MM DIA., PVC (SCHEDULE 80)	METER	345	140	80	125
M8170415	ELECTRICAL CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 1/C NO. 6	METER	990	360	290	340
M8170420	ELECTRICAL CABLE IN CONDUIT, 600V (EPR-TYPE RHW), 1/C NO. 8	METER	495	180	145	170
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	93	25	57	11
MX810070	CONDUIT IN TRENCH, 75MM DIA., PVC, SCHEDULE 80	METER	93	25	57	11
X8250100	LIGHTING CONTROLLER, 100 AMP, POLE MOUNTED	EACH	3	1	1	1
X8410105	TEMPORARY LIGHTING SYSTEM	EACH	2	1	0	1
XX002059	REMOVAL OF EXISTING LIGHTING UNIT - COMPLETE	EACH	6	2	0	4

TS-20

\$FILE\$ 9/15/2010 \$TIME\$


**AMES Engineering, Inc.**  
 Consulting Engineers  
 1341 Warren Avenue  
 Downers Grove, IL 60515

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: NONE  
DATE: MARCH, 2009

DRAWN BY: RV  
DESIGNED BY: AS/SM  
CHECKED BY: MSA