

TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)

LOCATION	EACH
FAI 74 EB	
LT. STA. 624+61.75 TO LT. STA. 625+05.50	1
LT. STA. 625+77.50 TO LT. STA. 626+21.25	1
TOTAL = 2	

GUARDRAIL REMOVAL

LOCATION	FOOT
FAI 55 NB	
LT. STA. 623+43 TO LT. STA. 625+55	212
RT. STA. 623+50 TO RT. STA. 624+92	142
RT. STA. 627+40 TO RT. STA. 643+68	1628
LT. STA. 627+92 TO LT. STA. 643+38	1546
LT. STA. 645+04 TO LT. STA. 651+48	644
RT. STA. 645+20 TO RT. STA. 651+66	646
FAI 74 EB	
LT. STA. 622+00 TO LT. STA. 626+58	458
RT. STA. 623+04 TO RT. STA. 626+42	338
BUSINESS FAI 55 SB	
LT. STA. 65+33 TO LT. STA. 71+64	631
RT. STA. 63+00 TO RT. STA. 71+27	827
TOTAL = 7072	

DELINEATORS

LOCATION	COLOR	EACH
RT. STA. 606+78 TO RT. STA. 623+37	YELLOW	12
LT. STA. 611+00 TO LT. STA. 623+16	WHITE	9
RT. STA. 653+89 TO RT. STA. 658+24	YELLOW	4
LT. STA. 653+00 TO LT. STA. 656+00	WHITE	3
TOTAL = 28		

DELINEATORS REMOVAL

LOCATION	EACH
QUANTITY ASSUMED TO BE SAME AS NEW DELINEATORS. (SEE SCHEDULE FOR DELINEATORS FOR LOCATIONS.)	28
TOTAL = 28	

SHOULDER RUMBLE STRIP (EXCLUDING STRUCTURES)

LOCATION	FOOT
FAI 55	
RT. STA. 606+77.56 TO RT. STA. 624+63	1785
LT. STA. 610+95 TO LT. STA. 625+15	1420
BRIDGE OMISSION SN 057-0250	
RT. STA. 628+20 TO RT. STA. 643+10	1490
LT. STA. 628+60 TO STA. 643+00	1440
BRIDGE OMISSION SN 057-0249	
RT. STA. 645+70 TO RT. STA. 664+00	1830
LT. STA. 645+60 TO LT. STA. 656+00	1040
FAI 74 EB	
LT. & RT. STA. 623+98.36 TO STA. 627+58.36	720
BUSINESS FAI 55 SB	
LT. & RT. STA. 69+46.60 TO STA. 73+36.60	780
BUSINESS FAI 55 NB	
LT. STA. 80+30 TO LT. STA. 90+45	1015
TOTAL = 11,520	

CONCRETE SHOULDER CURB

LOCATION	FOOT
RT. STA. 624+27 TO RT. STA. 624+37	10
RT. STA. 646+05 TO RT. STA. 646+15	10
TOTAL = 20	

NON-SPECIAL WASTE DISPOSAL

(PROVIDED BY DISTRICT @ SN 057-0005)
TOTAL = 600 CU. YD.

SPECIAL WASTE PLANS AND REPORT

(PROVIDED BY DISTRICT @ SN 057-0005)
TOTAL = 1 L SUM

SOIL DISPOSAL ANALYSIS

(PROVIDED BY DISTRICT @ SN 057-0005)
TOTAL = 1 EACH

ENGINEER'S FIELD OFFICE, TYPE B

LOCATION	CAL MO
SECTION (57-7HB-2 & 57-7HB-1)BR	12
TOTAL = 12	

MOBILIZATION

LOCATION	L SUM
SECTION (57-7HB-2 & 57-7HB-1)BR	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701421

LOCATION	L SUM
SECTION (57-7HB-2 & 57-7HB-1)BR	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701411

LOCATION	EACH
BUSINESS FAI 55 SB	1
I-74 WB TO BUSN. 55 SB RAMP	
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701406

LOCATION	L SUM
SECTION (57-7HB-2 & 57-7HB-1)BR	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701401

LOCATION	L SUM
SECTION (57-7HB-2 & 57-7HB-1)BR	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR
TWO LOCATIONS TO BE PAID FOR AS A SINGLE PAY ITEM FROM DISTRICT.

LOCATION	EACH
(NIGHT TIME CLOSURES) DETOUR FOR I-74 EB TRAFFIC	1
DETOUR FOR I-55 BUSN. SB TRAFFIC	
TOTAL = 1	

TRAFFIC CONTROL COMPLETE

LOCATION	L SUM
SECTION (57-7HB-2 & 57-7HB-1)BR	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 1

LOCATION	EACH
FAI 74 EB UNDER SN 057-0250	1
TOTAL = 1	

TRAFFIC CONTROL AND PROTECTION (SPECIAL), LOCATION 2

LOCATION	EACH
BUSINESS FAI 55 SB UNDER SN 057-0249	1
TOTAL = 1	

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
FAI 55 NB (STAGE I) STA. 606+77.56 TO STA. 660+20	5337.50
BUS 55 NB (STAGE I) STA. 81+95 TO STA. 85+45	350.00
FAI 74 EB (TC&P (SPL) LOCATION 1) LT., STA. 623+75 TO LT., STA. 626+00	225.00
RT., STA. 623+90 TO RT., STA. 626+52.5	262.50
BUSINESS FAI 55 SB (TC&P (SPL) LOCATION 2) LT., STA. 69+85 TO LT., STA. 71+72.5	187.50
RT., STA. 69+65 TO RT., STA. 71+52.5	187.50
TOTAL = 6550	

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
FAI 55 NB (STAGE II) STA. 606+77.56 TO STA. 660+90	5412.50
TOTAL = 5412.50	

URETHANE PAVEMENT MARKING - LINE 4"

LOCATION	LINE TYPE	FOOT
FAI 55 NB		
RT. STA. 606+78 TO STA. 618+35	EDGE LINE (YELLOW)	1157
LT. STA. 611+40 TO STA. 618+35	EDGE LINE (WHITE)	695
LT. STA. 618+35 TO STA. 649+10	EDGE LINE (WHITE)	3075
STA. 618+35 TO STA. 649+10	SKIP-DASH (WHITE)	770
RT. STA. 618+35 TO STA. 649+10	EDGE LINE (YELLOW)	3075
RT. STA. 649+10 TO STA. 664+00	EDGE LINE (YELLOW)	1490
LT. STA. 649+10 TO STA. 655+60	EDGE LINE (WHITE)	650
BUSINESS FAI 55 NB		
LT. STA. 80+30 TO STA. 90+45	EDGE LINE (WHITE)	1015

LOCATION	LINE TYPE	FOOT
FAI 74 EB (RUNDOWN REMOVAL)		
LT. STA. 623+98 TO STA. 627+58	EDGE LINE (YELLOW)	360
RT. STA. 623+98 TO STA. 627+58	EDGE LINE (WHITE)	360
BUS FAI 55 SB (RUNDOWN REMOVAL)		
LT. STA. 69+47 TO STA. 73+37	EDGE LINE (YELLOW)	390
RT. STA. 69+47 TO STA. 73+37	EDGE LINE (WHITE)	390
TOTAL = 13427		

URETHANE PAVEMENT MARKING - LINE 8"

LOCATION	LINE TYPE	FOOT
FAI 55		
LT. STA. 606+78 TO STA. 611+40	EDGE LINE (WHITE)	462
LT. STA. 606+78 TO STA. 611+40	EDGE LINE (WHITE)	462
LT. STA. 655+60 TO STA. 663+20	EDGE LINE (WHITE)	760
LT. STA. 655+60 TO STA. 663+20	EDGE LINE (WHITE)	760
TOTAL = 2444		

URETHANE PAVEMENT MARKING - LINE 12"

LOCATION	LINE TYPE	FOOT
FAI 55		
LT. STA. 606+78 TO STA. 611+40	DIAGONAL (WHITE)	192
LT. STA. 655+60 TO STA. 663+20	DIAGONAL (WHITE)	324
TOTAL = 516		

* INCLUDED IN THE COST OF VARIOUS TRAFFIC CONTROL ITEMS. SCHEDULES SHOWN FOR INFORMATION ONLY.

*** SHORT-TERM PAVEMENT MARKING**

LOCATION	FOOT
PLACED AFTER REMOVAL & REPLACEMENT OF THE EXISTING HMA SURFACE OF THE DRIVING LANES AS SHOWN IN THESE PLANS.	
STA. 606+78 TO STA. 619+45	132
STA. 648+00 TO STA. 658+24	108
PLACED ON FINAL SURFACE BEFORE PLACEMENT OF TEMPORARY OR PERMANENT MARKINGS.	
STA. 606+78 TO STA. 658+24	520
TOTAL = 760	

*** TEMPORARY PAVEMENT MARKING - LINE 4"**

LOCATION	LINE TYPE	FOOT
FAI 55		
RT. STA. 606+78 TO STA. 664+00	EDGE LINE (YELLOW)	5722
STA. 606+78 TO STA. 669+50	SKIP-DASH (WHITE)	1570
LT. STA. 611+40 TO STA. 655+60	EDGE LINE (WHITE)	4420
FAI 74 EB		
LT. STA. 623+98.36 TO STA. 627+58.36	EDGE LINE (YELLOW)	360
STA. 623+98.36 TO STA. 627+58.36	SKIP-DASH (WHITE)	90
RT. STA. 623+98.36 TO STA. 627+58.36	EDGE LINE (WHITE)	360
BUSINESS FAI 55 SB		
LT. STA. 69+46.60 TO STA. 73+36.60	EDGE LINE (YELLOW)	390
STA. 69+46.60 TO STA. 73+36.60	SKIP-DASH (WHITE)	100
RT. STA. 69+46.60 TO STA. 73+36.60	EDGE LINE (WHITE)	390
BUSINESS FAI 55 NB		
LT. STA. 80+30 TO STA. 90+45	EDGE LINE (WHITE)	1015
STA. 80+30 TO STA. 90+45	SKIP-DASH (WHITE)	250
TOTAL = 14,667		

*** TEMPORARY PAVEMENT MARKING - LINE 8"**

LOCATION	LINE TYPE	FOOT
FAI 55		
LT. STA. 606+78 TO STA. 611+40	EDGE LINE (WHITE)	462
LT. STA. 606+78 TO STA. 611+40	EDGE LINE (WHITE)	462
LT. STA. 655+60 TO STA. 663+20	EDGE LINE (WHITE)	760
LT. STA. 655+60 TO STA. 663+20	EDGE LINE (WHITE)	760
TOTAL = 2444		

*** TEMPORARY PAVEMENT MARKING - LINE 12"**

LOCATION	LINE TYPE	FOOT
FAI 55		
LT. STA. 606+78 TO STA. 611+40	DIAGONAL (WHITE)	192
LT. STA. 655+60 TO STA. 663+20	DIAGONAL (WHITE)	324
TOTAL = 516		

*** WORK ZONE PAVEMENT MARKING REMOVAL**

LOCATION	SQ FT
SHORT-TERM PAVEMENT MARKING	253
TEMPORARY PAVEMENT MARKINGS	7035
TOTAL = 7288	