

DECATUR, ILLINOIS

ENGINEERS - CONSULTANTS

BLANK, WESSELINK, COOK & ASSOCIATES

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE 00II
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	292
20200100	EARTH EXCAVATION	CU YD	120
20300100	CHANNEL EXCAVATION	CU YD	430
20400800	FURNISHED EXCAVATION	CU YD	385
25000210	SEEDING, CLASS 2A	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	69
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	69
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	69
25100630	EROSION CONTROL BLANKET	SO YD	2081
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75
28000305	TEMPORARY DITCH CHECKS	FOOT	102
28000400	PERIMETER EROSION BARRIER	FOOT	880
28000500	INLET AND PIPE PROTECTION	EACH	1
28100107	STONE RIPRAP, CLASS A4	SO YD	1424
28200200	FILTER FABRIC	SO YD	1424
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	22
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	44
40600300	AGGREGATE (PRIME COAT)	TON	1
40600990	TEMPORARY RAMP	SO YD	66
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	26
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	46
44000100	PAVEMENT REMOVAL	SO YD	149
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	363
44004250	PAVED SHOULDER REMOVAL	SO YD	77
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	90
48203100	HOT-MIX ASPHALT SHOULDERS	TON	8
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	287
50300100	FLOOR DRAINS	EACH	14
50300225	CONCRETE STRUCTURES	CU YD	123.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	392.1
50300260	BRIDGE DECK GROOVING	SO YD	587
50300280	CONCRETE ENCASEMENT	CU YD	7.2
50300300	PROTECTIVE COAT	SO YD	754

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY RURAL TWO-LANE ROADWAY 80% FEDERAL 20% STATE 00II
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106240
50800515	BAR SPLICERS	EACH	474
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	1774
51202305	DRIVING PILES	FOOT	1774
51203200	TEST PILE METAL SHELLS	EACH	3
51500100	NAME PLATES	EACH	1
54205470	PIPE CULVERTS, CLASS D, TYPE I EQUIVALENT ROUND-SIZE 15"	FOOT	40
54214290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	2
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	37
20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	124
61100605	MISCELLANEOUS CONCRETE	CU YD	0.3
61139900	STORM SEWERS, SPECIAL 6"	FOOT	30
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250.0
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	409
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	25.0
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	14
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	74
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	966
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	690
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400.0
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	966
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2
78200405	GUARDRAIL MARKERS	EACH	6
78200500	BARRIER WALL MARKERS	EACH	4

* DENOTES SPECIALTY ITEM

FILE NAME = c:\p\work\psidot\keysrb\d011011\0570512	USER NAME = keysrb -sh1-500.dgn	DESIGNED - DRAWN -	REVISED - REVISED -
PLOT SCALE = 40.000 / IN.	PLOT DATE = 8/13/2010	CHECKED - DATE -	REVISED - REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.S. RTE. 2484	SECTION 124BR-1	COUNTY MCLEAN	TOTAL SHEETS 55	SHEET NO. 3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70612	