

DECATUR, ILLINOIS

ENGINEERS - CONSULTANTS

BLANK, WESSELINK, COOK & ASSOCIATES

URBAN

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STP 80% FEDERAL 20% STATE 0011
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1228
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	187
20200100	EARTH EXCAVATION	CU YD	510
20400800	FURNISHED EXCAVATION	CU YD	6720
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	176.8
25000200	SEEDING, CLASS 2	ACRE	1.00
25000300	SEEDING, CLASS 3	ACRE	1.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	204
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	204
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	204
25100115	MULCH, METHOD 2	ACRE	1.00
25100630	EROSION CONTROL BLANKET	SO YD	5591
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	225
28000315	AGGREGATE DITCH CHECKS	TON	1
28000400	PERIMETER EROSION BARRIER	FOOT	4347
28000500	INLET AND PIPE PROTECTION	EACH	3
28100107	STONE RIPRAP, CLASS A4	SO YD	422
28200200	FILTER FABRIC	SO YD	422
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SO YD	244
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	128
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	46
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	511
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	623
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	42
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SO YD	16
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	3764
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	519
44000400	GUTTER REMOVAL	FOOT	3514
Z0004552	APPROACH SLAB REMOVAL	SO YD	106
44004000	PAVED DITCH REMOVAL	FOOT	13
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SO YD	100

URBAN

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY STP 80% FEDERAL 20% STATE 0011
48101200	AGGREGATE SHOULDERS, TYPE B	TON	728
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1824
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	11
50157300	PROTECTIVE SHIELD	SO YD	602
50200100	STRUCTURE EXCAVATION	CU YD	424
50300225	CONCRETE STRUCTURES	CU YD	256
50300255	CONCRETE SUPERSTRUCTURE	CU YD	498.4
50300260	BRIDGE DECK GROOVING	SO YD	1249
50300280	CONCRETE ENCASMENT	CU YD	4.2
50300300	PROTECTIVE COAT	SO YD	1625
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	3402
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	158,980
50800515	BAR SPLICERS	EACH	76
51100100	SLOPE WALL 4 INCH	SO YD	516
51201500	FURNISHING STEEL PILES HPI0X57	FOOT	702
51201600	FURNISHING STEEL PILES HPI2X53	FOOT	1560
51202305	DRIVING PILES	FOOT	2262
51204650	PILE SHOES	EACH	60
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	48
54213447	END SECTIONS 12"	EACH	4
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 112"	FOOT	360
550A0160	STORM SEWERS, CLASS A, TYPE 136"	FOOT	29
55100500	STORM SEWER REMOVAL 12"	FOOT	133
55100700	STORM SEWER REMOVAL 15"	FOOT	24
55101200	STORM SEWER REMOVAL 24"	FOOT	17
55201300	STORM SEWERS JACKED IN PLACE, 36"	FOOT	93
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	136

• DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = laughlinr1	DESIGNED - CWC	REVISED -
c:\pw\work\pwwork\laughlinr1\d0232385\DE	2692-shr-500.dgn	DRAWN - BWC	REVISED -
	PLOT SCALE = 40.000' / 1"	CHECKED - RMD	REVISED -
	PLOT DATE = Aug-12-2010 11:43:54AM	DATE - 02/09/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8159	110X-3VB-4	SANGAMON	78	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72692	

Rev.