

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE						
					0004 ROADWAY	0011 STRUCTURE S.N. 034-2525	0011 STRUCTURE S.N. 034-2526				
20200100	EARTH EXCAVATION	.	CU YD	1070	1070						
20300100	CHANNEL EXCAVATION		CU YD	534	534						
20400800	FURNISHED EXCAVATION		CU YD	250	250						
20800150	TRENCH BACKFILL		CU YD	37	37						
25000200	SEEDING, CLASS 2		ACRE	1.50	1.50						
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	135	135						
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	135	135						
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	135	135						
25000700	AGRICULTURAL GROUND LIMESTONE		TON	3.0	3.0						
25100115	MULCH, METHOD 2		ACRE	1.50	1.50						
25100635	HEAVY DUTY EROSION CONTROL BLANKET		SQ YD	135	135						
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	300	300						
28000400	PERIMETER EROSION BARRIER		FOOT	1070	1070						
28000500	INLET AND PIPE PROTECTION		EACH	3	3						
28001000	AGGREGATE (EROSION CONTROL)		TON	12	12						
28100709	STONE DUMPED RIPRAP, CLASS A5	.	SO YD	2304	2007	124	173				
35101400	AGGREGATE BASE COURSE, TYPE B		TON	100	100						
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	.	SO YD	2998	2998						
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	.	SO YD	192	192						
40201000	AGGREGATE FOR TEMPORARY ACCESS		TON	20	20						
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	4.0	4.0						
40600300	AGGREGATE (PRIME COAT)		TON	22	22						
40600625	LEVELING BINDER (MACHINE METHOD), N50		TON	276	276						
40600895	CONSTRUCTING TEST STRIP		EACH	2	2						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		SO YD	332	332						
40600990	TEMPORARY RAMP	.	SO YD	190	190						