

| SUMMARY OF QUANTITIES |                                                    |           |                  |                  | 80% FED.<br>20% STATE | CONSTRUCTION AND SAFETY TYPE CODE  |                                    |  |  |  |
|-----------------------|----------------------------------------------------|-----------|------------------|------------------|-----------------------|------------------------------------|------------------------------------|--|--|--|
| CODE NO.              | ITEM                                               | SP. PROV. | UNIT             | TOTAL QUANTITIES | 0004<br>ROADWAY       | 0011<br>STRUCTURE<br>S.N. 034-2525 | 0011<br>STRUCTURE<br>S.N. 034-2526 |  |  |  |
| 40603080              | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50        |           | TON              | 1494             | 1494                  |                                    |                                    |  |  |  |
| 40603310              | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50       |           | TON              | 444              | 444                   |                                    |                                    |  |  |  |
| 40800050              | INCIDENTAL HOT-MIX ASPHALT SURFACING               |           | TON              | 95               | 95                    |                                    |                                    |  |  |  |
| 42001300              | PROTECTIVE COAT                                    |           | SO YD            | 34               | 34                    |                                    |                                    |  |  |  |
| 42300200              | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH |           | SO YD            | 37               | 37                    |                                    |                                    |  |  |  |
| 44000100              | PAVEMENT REMOVAL                                   |           | SO YD            | 139              | 139                   |                                    |                                    |  |  |  |
| 44000200              | DRIVEWAY PAVEMENT REMOVAL                          |           | SO YD            | 130              | 130                   |                                    |                                    |  |  |  |
| 44000400              | GUTTER REMOVAL                                     |           | FOOT             | 440              | 440                   |                                    |                                    |  |  |  |
| 44004250              | PAVED SHOULDER REMOVAL                             |           | SO YD            | 1879             | 1879                  |                                    |                                    |  |  |  |
| 44200099              | PAVEMENT PATCHING, TYPE III, 8 INCH                |           | SO YD            | 24               | 24                    |                                    |                                    |  |  |  |
| 44200101              | PAVEMENT PATCHING, TYPE IV, 8 INCH                 |           | SO YD            | 27               | 27                    |                                    |                                    |  |  |  |
| 48101200              | AGGREGATE SHOULDERS, TYPE B                        |           | TON              | 163              | 163                   |                                    |                                    |  |  |  |
| X4811300              | AGGREGATE SHOULDERS, TYPE B (SPECIAL)              | .         | TON              | 153              | 153                   |                                    |                                    |  |  |  |
| 48203100              | HOT-MIX ASPHALT SHOULDERS                          |           | TON              | 686              | 686                   |                                    |                                    |  |  |  |
| 50100300              | REMOVAL OF EXISTING STRUCTURES NO. 1               | .         | EACH             | 1                |                       | 1                                  |                                    |  |  |  |
| 50100400              | REMOVAL OF EXISTING STRUCTURES NO. 2               | .         | EACH             | 1                |                       |                                    | 1                                  |  |  |  |
| 50105220              | PIPE CULVERT REMOVAL                               | *         | FOOT             | 126              | 126                   |                                    |                                    |  |  |  |
| <del>50200100</del>   | <del>STRUCTURE EXCAVATION</del>                    |           | <del>CU YD</del> | <del>1710</del>  |                       | <del>690</del>                     | <del>1020</del>                    |  |  |  |
| 50500105              | FURNISHING AND ERECTING STRUCTURAL STEEL           |           | L SUM            | 1                |                       |                                    | 1                                  |  |  |  |
| 50800105              | REINFORCEMENT BARS                                 |           | POUND            | 3580             |                       | 1320                               | 2260                               |  |  |  |
| 51500100              | NAME PLATES                                        |           | EACH             | 2                |                       | 1                                  | 1                                  |  |  |  |
| 54001001              | BOX CULVERT END SECTION, CULVERT NO.1              |           | EACH             | 2                |                       | 2                                  |                                    |  |  |  |
| 54001002              | BOX CULVERT END SECTION, CULVERT NO.2              |           | EACH             | 2                |                       |                                    | 2                                  |  |  |  |
| 54020705              | PRECAST CONCRETE BOX CULVERT 7' X 5' (M273)        |           | FOOT             | 209.0            |                       | 209.0                              |                                    |  |  |  |
| 54021107              | PRECAST CONCRETE BOX CULVERT 11' X 7' (M273)       |           | FOOT             | 210.5            |                       |                                    | 210.5                              |  |  |  |
| 542A0220              | PIPE CULVERTS, CLASS A, TYPE 1 15"                 |           | FOOT             | 12               | 12                    |                                    |                                    |  |  |  |

Rev.