

| SUMMARY OF QUANTITIES | | | | | 80% FED. 20% STATE TOTAL QUANTITIES | CONSTRUCTION AND SAFETY TYPE CODE | | | | |
|-----------------------|---|-----------|-----------------|--|--|-----------------------------------|-----------------------------------|--------------|--|--|
| CODE NO. | ITEM | SP. PROV. | UNIT | | 0004 ROADWAY | 001 STRUCTURE S.N. 034-2525 | 001 STRUCTURE S.N. 034-2526 | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | | SO FT | | 5970 | 5970 | | | | |
| 70400100 | TEMPORARY CONCRETE BARRIER | | FOOT | | 675 | 675 | | | | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | | FOOT | | 337.5 | 337.5 | | | | |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | | EACH | | 23 | 23 | | | | |
| * 78200410 | GUARDRAIL MARKERS, TYPE A | * | EACH | | 18 | 18 | | | | |
| * 78201000 | TERMINAL MARKER - DIRECT APPLIED | * | EACH | | 4 | 4 | | | | |
| 78300100 | PAVEMENT MARKING REMOVAL | | SO FT | | 1934 | 1934 | | | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | | EACH | | 23 | 23 | | | | |
| Z0013798 | CONSTRUCTION LAYOUT | * | L SUM | | 1 | 1 | | | | |
| Z0030260 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | * | EACH | | 4 | 4 | | | | |
| Z0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | * | EACH | | 4 | 4 | | | | |
| * Z0054517 | ROCK FILL - FOUNDATION | * | TON | | 555 | | 265 | 290 | | |
| Z0073002 | TEMPORARY SOIL RETENTION SYSTEM | * | SO FT | | 360 | | 195 | 165 | | |
| Z0023602 | GRANULAR CULVERT BACKFILL | * | CU YD | | 422 | | 181 | 241 | | |
| X0327069 | TREE REMOVAL | * | L SUM | | 1 | 1 | | | | |
| X5020501 | UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 1 | | EACH | | 1 | | 1 | | | |
| X5020502 | UNDERWATER STRUCTURE EXCAVATION PROTECTION LOCATION 2 | | EACH | | 1 | | | 1 | | |
| X7200201 | WIDTH RESTRICTION SIGNING | * | L SUM | | 1 | 1 | | | | |
| * X7800620 | URETHANE PAVEMENT MARKING - LINE 5" | * | FOOT | | 6344 | 6344 | | | | |
| * X7800680 | URETHANE PAVEMENT MARKING - LINE 24" | * | FOOT | | 25 | 25 | | | | |
| X0358300 | REMOVE AND RELAY END SECTIONS | * | EACH | | 1 | 1 | | | | |
| X0301852 | DEWATERING STRUCTURE NO. 1 | * | EACH | | 1 | | 1 | | | |
| X0301853 | DEWATERING STRUCTURE NO. 2 | * | EACH | | 1 | | 1 | | | |

*Specialty Items

Rev.

| | | | | | | | | | | | | |
|---|---------------------------|------------|-----------|---|-----------------------|---------------|----------|---------------------|----------------|---------------------------|-----------------|--------------|
| FILE NAME = | USER NAME = laughlinr1 | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| ca:\pwwork\pwwork\laughlinr1\0229631\Su | Summary of Quantities.dgn | DRAWN - | REVISED - | | | | | 510 | 120 (B-4, B-5) | HANCOCK | 80 | 6 |
| PLOT SCALE = 100.0000 "/ in. | CHECKED - | REVISED - | REVISED - | | CONTRACT NO. 72A65 | | | FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| PLOT DATE = Aug-18-2010 02:36:20PM | DATE - | REVISED - | REVISED - | | SCALE: none | SHEET NO. 40F | 4 SHEETS | STA. | TO STA. | | | |