

SUMMARY OF QUANTITIES					80% FED. 20% STATE TOTAL QUANTITIES		% FEDERAL % STATE CONSTRUCTION AND SAFETY TYPE CODE			
CODE NO.	ITEM	SP. PROV.	UNIT			0004 ROADWAY	0011 STRUCTURE			
50100100	REMOVAL OF EXISTING STRUCTURES		EACH		1		1			
50200100	STRUCTURE EXCAVATION		CU YD		225		225			
50300100	FLOOR DRAINS		EACH		20		20			
50300225	CONCRETE STRUCTURES		CU YD		134.9		134.9			
50300255	CONCRETE SUPERSTRUCTURE		CU YD		311.0		311.0			
50300260	BRIDGE DECK GROOVING		SO YD		759		759			
50300280	CONCRETE ENCASEMENT		CU YD		11.2		11.2			
50300300	PROTECTIVE COAT		SO YD		982		982			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL		L SUM		1		1			
50500505	STUD SHEAR CONNECTORS		EACH		3240		3240			
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND		93750		93750			
50800515	BAR SPLICERS		EACH		918		918			
51201610	FURNISHING STEEL PILES HP12X63		FOOT		1575		1575			
51202305	DRIVING PILES		FOOT		1575		1575			
51203610	TEST PILE STEEL HP12X63		EACH		4		4			
51500100	NAME PLATES		EACH		1		1			
52100520	ANCHOR BOLTS, 1"		EACH		48		48			
59100100	GEOCOMPOSITE WALL DRAIN		SO YD		70		70			
60100060	CONCRETE HEADWALL FOR PIPE DRAINS		EACH		4		4			
<b>20046304</b>	PIPE UNDERDRAINS FOR STRUCTURES 4"		FOOT		134		134			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		FOOT		400.00	400.00				
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2		EACH		1	1				
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		EACH		4	4				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		EACH		2	2				
63200310	GUARDRAIL REMOVAL		FOOT		515	515				
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)		FOOT		25.00	25.00				
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO		8	8				
67100100	MOBILIZATION		L SUM		1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM		1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		L SUM		1	1				

*\*Specialty Items*

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\laughlinr1\d0231868\0672853-sht-500.dgn	DRAWN -	REVISED -	608					122B-2	MACOUPIN	53	4	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	SCALE: NONE SHEET NO. 20F 35SHEETS STA. TO STA.					CONTRACT NO. 72B53				
PLOT DATE = Aug-11-2010 03:41:19PM	DATE -	REVISED -	FED. ROAD DIST. NO. 6					ILLINOIS FED. AID PROJECT				