

SCHEDULE OF QUANTITIES

REMOVAL SCHEDULE

	Sta.	to	Sta.	Distance	PAVEMENT REMOVAL SQ YD	GUTTER REMOVAL FOOT	PAVED SHLDR REM SQ YD	PIPE CULV REM FOOT
Mainline	129+90.00		130+50.00	60.00				
	130+50.00		131+03.00	53.00	153			
	131+79.00		132+20.00	41.00	118			
	132+20.00		133+67.40	147.40				
Rt Shldr	130+52.00		131+03.00	51.00			23	
	131+79.00		132+24.00	45.00			20	
	132+24.00		138+50.00	626.00		626		
Lt Shldr	130+48.00		131+03.00	55.00			24	
	131+79.00		132+28.00	49.00			22	
	134+00.00		138+50.00	450.00		450		
Red Bridge Rd.	127+60.00	RT			190			50
Entrances	135+61.50	RT	CE					
	135+92.00	LT	PE		286			
			TOTALS=		748	1,076	89	50

GUARDRAIL SCHEDULE

LOCATION				SPBGR, TY A, 6' POSTS	TRAF BAR TERM, TY 1 (SPCL)	TRAF BAR TERM, TY 6	TEMP TRAF BAR TERM, TY 1, SPCL, (TANGENT)	GUARDRAIL REMOVAL FOOT
Sta	to	Sta		FOOT	EACH	EACH	EACH	FOOT
128+42.80	to	128+67.80	LT, Stage 3		1			
128+67.80	to	130+05.30	LT, Stage 3	137.50				
129+80.30	to	130+05.30	LT, Stage 1				1	
130+05.30	to	130+48.44	LT, Stage 1			1		
129+65.00	to	133+17.00	LT, Stage 1					352
132+18.86	to	132+62.00	LT, Stage 1			1		
132+62.00	to	132+87.00	LT, Stage 1				1	
132+62.00	to	134+74.50	LT, Stage 3	212.50				
134+74.50	to	134+99.50	LT, Stage 3		1			
128+14.90	to	128+39.90	RT, Stage 3		1			
128+39.90	to	130+14.90	RT, Stage 3	175.00				
129+89.90	to	130+14.90	RT, Stage 2				1	
130+14.90	to	130+58.04	RT, Stage 2			1		
129+65.00	to	133+17.00	RT, Stage 2					352
132+28.46	to	132+71.60	RT, Stage 2			1		
132+71.60	to	132+96.60	RT, Stage 2				1	
132+71.60	to	134+09.10	RT, Stage 3	137.50				
134+09.10	to	134+34.10	RT, Stage 3		1			
			TOTAL=	662.5	4	4	4	704

GUTTER SCHEDULE

Sta	to	Sta		Length	Area (sf)	CLASS SI CONCRETE (OUTLET) CU YD	CONCRETE GUTTER TYPE A FOOT
136+36.70		136+64.00	RT	25.94	2.00	1.9	
136+64.00		137+20.00	RT		na	4.6	
137+20.00		138+50.00	RT	130.00			130
136+61.30		136+92.00	LT	33.30	2.00	2.5	
136+92.00		137+50.00	LT		na	4.6	
137+50.00		138+50.00	LT	100.00			100
			TOTALS=			13.6	230

EARTHWORK SCHEDULE

LOCATION			EARTH EXCAVATION CU YD	CHANNEL EXCAVATION CU YD	EARTH EXCAVATION & CHANNEL EXCAVATION ADJUSTMENT FOR SHRINKAGE CU YD	EMBANKMENT (FILL) CU YD	EARTH BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION) CU YD
PRE STAGE I							
124+50.00	to	130+60.00	27		20	0	20
132+17.00	to	139+00.00	1,728		1,296	1,781	-485
STAGE I							
124+50.00	to	130+69.24	848		636	761	-125
132+17.00	to	139+00.00	3,816		2,862	2,140	722
STAGE II							
124+50.00	to	130+69.24	1,066		800	599	201
132+17.00	to	139+00.00	0		0	212	-212
STAGE III							
124+50.00	to	130+69.24	0		0	0	0
132+17.00	to	139+00.00	130		98	517	-420
CHANNEL EXCAVATION							
00+00	to	2+00.00		3,741	2,806	3	2,803
		TOTAL=	7,615	3,741	8,517	6,013	2,504

EARTH EMBANKMENT SHRINKAGE FACTOR = 25%

DRAINAGE SCHEDULE

LOCATION			PIPE DRAINS, 12"	PIPE CULV, CLASS A, TYPE 2, 24"	PIPE CULV, CLASS D, TYPE 2, 24"	METAL END SECTIONS 12"	METAL END SECTIONS 24"	PRECAST CONC FLARED END SECTION, 24"	TYPE B INLET BOX, 609001
Sta	to	Sta	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH
127+37.05	to	127+89.50	RT	58				2	
130+23.33			LT	11		1			1
130+32.97			RT	11		1			1
135+36.70	to	136+50.40	RT		89		2		
135+61.30	to	136+76.40	LT		88		2		
		TOTAL=		22	58	177	2	4	2

FILE NAME : P:\0807402-106 over Sandy creek\CADD	USER NAME : default	DESIGNED - E.R.O.	REVISED -
CADD sheets\0672891-sht-schedule.dgn	PLOT SCALE : 2.0000' / IN.	DRAWN - R.A.W.	REVISED -
PLOT DATE : 9/17/2018		CHECKED - J.S.A.	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 566	SECTION 1(B-2)	COUNTY SCOTT	TOTAL SHEETS 77	SHEET NO. 6
CONTRACT NO. 72891				
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				