

INDEX OF SHEETS

1	COVER SHEET
2	INDEX, STANDARDS, & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	STAGING DETAILS
5-13	BRIDGE PLANS & ELEVATION VIEWS

STANDARDS

701101 -02
701106 -02
701400 -04
701402 -07
701901 -01
704001 -06
701406-05

GENERAL NOTES:

PRIOR TO POURING THE NEW CONCRETE JOINTS, ALL HEAVY OR LOOSE RUST, LOOSE MILL SCALE, AND OTHER LOOSE OR POTENTIALLY DETRIMENTAL FOREIGN MATERIAL SHALL BE REMOVED FROM THE SURFACES IN CONTACT WITH CONCRETE. TIGHTLY ADHERED PAINT MAY REMAIN UNLESS OTHERWISE NOTED. REMOVAL SHALL BE ACCOMPLISHED BY METHODS THAT WILL NOT DAMAGE THE STEEL AND THE COST WILL BE INCLUDED IN THE PAY ITEM COVERING REMOVAL OF EXISTING CONCRETE.

THE DECK SURFACE SHALL HAVE ITS FINAL FINISH TINED ACCORDING TO ARTICLE 420.09(E)(1) OF THE STANDARD SPECIFICATIONS. COST INCLUDED WITH CONCRETE SUPERSTRUCTURE.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>SEP 7</u>	20 <u>10</u>
<i>Carl Walker</i> ENGINEER OF OPERATIONS	
EXAMINED <u>SEPT 7</u>	20 <u>10</u>
<i>Tommy Ford</i> ENGINEER OF PROGRAM IMPLEMENTATION	
EXAMINED <u>Sept 7</u>	20 <u>10</u>
<i>ARMU</i> ENGINEER OF PROGRAM DEVELOPMENT	

INDEX, STDS, & GENERAL NOTES
FAI 72 (I-72)
SECTION (75,86)BJR
PIKE COUNTY

Rev.