

INDEX OF SHEETS:

- 1 COVER SHEET
- 2 INDEX, GENERAL NOTES, & STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 EXISTING PLAN & ELEVATION
- 5-6 TRAFFIC CONTROL PLANS
- 7 EXISTING CROSS SECTIONS
- 8 REMOVAL DETAILS
- 9 PROPOSED REINFORCEMENT
- 10 STRIP SEAL JOINT DETAILS
- 11 BAR SPLICER DETAILS

STANDARDS

- 701101-02
- 701106-02
- 701400-04
- ~~701402 (SPECIAL)~~
- 701406-05
- 701446-01
- 701901-01
- 704001-06

GENERAL NOTES:

REINFORCEMENT BARS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 706 GR 60. SEE SPECIAL PROVISIONS.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED BASED UPON THE UNIT PRICE BID FOR THE WORK.

EXISTING REINFORCEMENT BARS EXTENDING INTO THE REMOVAL AREA SHALL BE CLEANED, STRAIGHTENED, AND INCORPORATED INTO THE NEW CONSTRUCTION. ANY REINFORCEMENT BARS THAT ARE DAMAGED DURING CONCRETE REMOVAL SHALL BE REPLACED WITH AN APPROVED BAR SPLICER OR ANCHORAGE SYSTEM. COST INCLUDED WITH CONCRETE REMOVAL.

JOINT OPENINGS SHALL BE ADJUSTED ACCORDING TO ARTICLE 520.04 OF THE STD SPECS WHEN THE DECK IS POURED AT AN AMBIENT TEMPERATURE OTHER THAN 50 DEG F.

REINFORCEMENT BARS DESIGNATED (E) SHALL BE EPOXY COATED.

PRIOR TO POURING THE NEW CONCRETE DECK, ALL HEAVY OR LOOSE RUST, LOOSE MILL SCALE, AND OTHER LOOSE OR POTENTIALLY DETRIMENTAL FOREIGN MATERIAL SHALL BE REMOVED FROM THE SURFACES IN CONTACT WITH CONCRETE. TIGHTLY ADHERED PAINT MAY REMAIN UNLESS OTHERWISE NOTED. REMOVAL SHALL BE ACCOMPLISHED BY METHODS THAT WILL NOT DAMAGE THE STEEL AND THE COST WILL BE INCLUDED IN THE PAY ITEM COVERING REMOVAL OF EXISTING CONCRETE.

THE DECK SURFACE SHALL HAVE ITS FINAL FINISH TINED ACCORFDING TO ARTICLE 420.09(EX1) OF THE STANDARD SPECIFICATIONS. COST INCLUDED WITH CONCRETE SUPERSTRUCTURE

ASPHALT MIXTURE TABLE

MIX USE	PG	DESIGN AIR VOIDS	MIXTURE COMPOSITION (GRADATION MIXTURE)	FRICTION AGGREGATE
HMA SURF.	SBS PG76-22	4.0% @ N DESIGN = 105	IL 9.5 OR 12.5	MIX "E"
HMA SHLDR.	PG64-22	4.0% @ N DESIGN = 50	IL 9.5 OR 12.5	MIX "E"

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6

EXAMINED JULY 12 20 10

Chris Walker

ENGINEER OF OPERATIONS

EXAMINED AUGUST 4 20 10

Jimmy Felt

ENGINEER OF PROGRAM IMPLEMENTATION

EXAMINED AUGUST 6 20 10

QRML

ENGINEER OF PROGRAM DEVELOPMENT

INDEX & GENERAL NOTES
SN 054-0042
EXP. JT. REPLACEMENT
LOGAN COUNTY

Rev.