

SUMMARY OF QUANTITIES				90% FED, 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				0003	0010
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75	
20200100	EARTH EXCAVATION	CU YD	823	823	
20400800	FURNISHED EXCAVATION	CU YD	7,046	7,046	
x2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	352		352
20900110	POROUS GRANULAR BACKFILL	CU YD	497	497	
25000210	SEEDING, CLASS 2A	ACRE	2.50	2.50	
25000350	SEEDING, CLASS 7	ACRE	2.50	2.50	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225	225	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225	225	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225	225	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	5.0	5.0	
25100115	MULCH, METHOD 2	ACRE	5.0	5.0	
25100630	EROSION CONTROL BLANKET	SQ YD	9,573	9,573	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	750	750	
28000305	TEMPORARY DITCH CHECKS	FOOT	40	40	
28000400	PERIMETER EROSION BARRIER	FOOT	6,099	6,099	
28000500	INLET AND PIPE PROTECTION	EACH	16	16	
28100105	STONE RIPRAP, CLASS A3	SQ YD	28	28	

SUMMARY OF QUANTITIES				90% FED, 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				0003	0010
28200200	FILTER FABRIC	SQ YD	2,640	28	2,612
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	12,432	12,432	
30201500	LIME	TON	239.4	239.4	
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	1,710	1,710	
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,664	3,664	
40600300	AGGREGATE (PRIME COAT)	TON	45	45	
40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
40600990	TEMPORARY RAMP	SQ YD	144	144	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7,099	7,099	
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	6,938	6,938	
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	2,096	2,096	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	140	140	
42001300	PROTECTIVE COAT	SQ YD	4,064	4,064	
x4201400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	814	814	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,130	1,130	
44000100	PAVEMENT REMOVAL	SQ YD	636	636	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	29,631	29,631	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	559	559	

* SPECIALTY ITEM