

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					L25 ACF		L1C ACSRF
					ROADWAY 0005 RURAL	BRIDGE 0011 RURAL	NP 100% STATE ROADWAY 0005 RURAL
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2,299	2,299		
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
	50104000	BRIDGE RAIL REMOVAL	FOOT	506		506	
	50200100	STRUCTURE EXCAVATION	CU YD	288		288	
	50200300	COFFERDAM EXCAVATION	CU YD	158		158	
	50202901	COFFERDAM (LOCATION - 1)	EACH	1		1	
	50300225	CONCRETE STRUCTURES	CU YD	142.4		142.4	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	477.8		477.8	
	50300260	BRIDGE DECK GROOVING	SQ YD	1,258		1,258	
	50300265	SEAL COAT CONCRETE	CU YD	66.4		66.4	
	50300280	CONCRETE ENCASEMENT	CU YD	8.8		8.8	
	50300300	PROTECTIVE COAT	SQ YD	1,334		1,334	
	50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
	50500505	STUD SHEAR CONNECTORS	EACH	2,556		2,556	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	131,460		131,460	
	50800515	BAR SPLICERS	EACH	1,152		1,152	
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	928		928	
	51201800	FURNISHING STEEL PILES HP14X73	FOOT	1,026		1,026	
	51202305	DRIVING PILES	FOOT	1,954		1,954	
	51203600	TEST PILE STEEL HP12X53	EACH	1		1	
	51203800	TEST PILE STEEL HP14X73	EACH	2		2	
	51204650	PILE SHOES	EACH	46		46	
	20026407	TEMPORARY SHEET PILING	SQ FT	1,471		1,471	
	51500100	NAME PLATES	EACH	1		1	
	52100520	ANCHOR BOLTS, 1"	EACH	36		36	
	59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	93		93	
	60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4	4		
	60100915	PIPE DRAINS 6"	FOOT	50	50		
	60100925	PIPE DRAINS 8"	FOOT	50	50		
	20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	180		180	
	61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2		
	63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	225	225		

FILE NAME = P:\DBBEL WEST Projects\2009\124100_409_IL48\Civil\Drawings\20094854-ht-5002.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 116 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = *USER*	DESIGNED -	REVISED -
PLLOT SCALE -	DRAWN -	REVISED -
PLLOT DATE = 7/28/2010	CHECKED -	REVISED -
	DATE - 8/6/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 4 OF 90 SHEETS	STA.	TO STA.

F.A.P. RTE. 646	SECTION BBR-1	COUNTY WHITEHIDE	TOTAL SHEETS 90	SHEET NO. 4
CONTRACT NO. 84854				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				