

**FAP 317 (US 24) West of
Astoria- Topsoil Availability**

Sta.	Offset*	Depth**
27+00	30' Lt	4"
27+00	40' Lt	0"
27+00	50' Lt	9"
27+00	27' Rt	6"
30+00	30' Lt	2"
30+00	35' Rt	6"
30+00	45' Rt	4"
40+00	40' Lt	2"
40+00	35' Rt	4"
40+00	45' Rt	8"
43+00	30' Rt	4"
55+00	35' Rt	2"
93+00	33' Lt	2"
93+00	45' Lt	0"
93+00	35' Rt	4"
95+00	35' Lt	0"
95+00	35' Rt	0"
97+00	35' Lt	0"
97+00	45' Lt	0"
97+00	35' Rt	4"
103+00	25' Lt	6"
103+00	25' Rt	6"
103+00	35' Rt	8"
104+00	25' Lt	6"
104+00	35' Lt	6"
104+00	25' Rt	0"
104+00	35' Rt	9"
107+00	40' Lt	4"
107+00	30' Rt	8"
113+00	30' Lt	4"
113+00	30' Rt	10"
115+00	30' Lt	10"
115+00	30' Rt	6"

**FAP 317 (US 24) West of
Astoria- Topsoil Availability**

Sta.	Offset*	Depth**
117+00	30' Lt	8"
117+00	30' Rt	10"
123+00	30' Lt	9"
123+00	30' Rt	12"
125+00	25' Lt	4"
125+00	35' Lt	10"
125+00	30' Rt	10"
132+00	30' Lt	2"
132+00	30' Rt	10"
135+00	35' Lt	8"
135+00	30' Rt	4"
138+00	25' Lt	0"
138+00	33' Lt	6"
138+00	25' Rt	0"
138+00	35' Rt	6"
142+00	30' Lt	6"
142+00	30' Rt	10"
149+00	50' Lt	0"
149+00	35' Rt	0"
151+00	35' Lt	4"
151+00	35' Rt	8"
164+00	25' Lt	0"
164+00	35' Lt	6"
164+00	25' Rt	0"
164+00	35' Rt	8"
181+00	30' Lt	6"
181+00	30' Rt	9"
191+00	30' Lt	6"
191+00	30' Rt	9"
196+00	25' Lt	0"
196+00	35' Lt	0"
196+00	25' Rt	0"
196+00	35' Rt	8"
202+00	25' Lt	0"
202+00	35' Lt	6"
202+00	25' Rt	0"
202+00	35' Rt	6"

**FAP 317 (US 24) West of
Astoria- Topsoil Availability**

Sta.	Offset*	Depth**
208+00	25' Lt	0"
208+00	35' Lt	4"
208+00	25' Rt	0"
208+00	35' Rt	4"
215+00	25' Lt	0"
215+00	35' Lt	0"
215+00	25' Rt	0"
215+00	35' Rt	4"
223+00	25' Lt	0"
223+00	35' Lt	10"
223+00	25' Rt	0"
223+00	35' Rt	10"

* Offset from centerline

** Depth represents available topsoil after stripping 2" of vegetation, roots

FOR INFORMATION ONLY

FILE NAME = miscellaneous.sheet.dgn	USER NAME = russellm	DESIGNED - KJH	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TOPSOIL SURVEY (FOR INFO ONLY)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - JGJ	REVISOR -			317	15W-2,RS-3,16W-3,RS-5	FULTON	171	90	
PLOT SCALE = 100.0000' / IN.	CHECKED - KJH	REVISOR -				CONTRACT NO. 88098					
PLOT DATE = 8/10/2010	DATE -	REVISOR -				SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT