

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
00-P4002-03-B1		PEORIA	53	6
STA. 100+36.27 TO STA. 179+51.94				
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH			42400100
LOCATION	DESCRIPTION	QUANTITY	
STATION TO STATION		SO FT	
STA. 134+30.06 TO STA. 134+36.06	RAMP & SIDEWALK	99	
STA. 134+69.62 TO STA. 134+75.62	RAMP & SIDEWALK	91	
GILES/KNOXVILLE - NORTHWEST QUADRANT	RAMP & SIDEWALK	1111	
GILES/KNOXVILLE - NORTHEAST QUADRANT	RAMP	109	
STA. 152+06.80 TO STA. 152+20.62	RAMP	200	
TOTAL		1610	

COMBINATION CURB AND GUTTER REMOVAL			44000500
LOCATION	DESCRIPTION	QUANTITY	
STATION TO STATION		FOOT	
GILES/KNOXVILLE - NORTHWEST QUADRANT	CURB AND GUTTER	142	
GILES/KNOXVILLE - SOUTHWEST QUADRANT	CURB AND GUTTER	104	
GILES/KNOXVILLE - NORTHEAST QUADRANT	CURB AND GUTTER	18	
TOTAL		264	

SIDEWALK REMOVAL			44000600
LOCATION	DESCRIPTION	QUANTITY	
STATION TO STATION		SO FT	
GILES/KNOXVILLE - NORTHWEST QUADRANT	SIDEWALK	895	
GILES/KNOXVILLE - NORTHEAST QUADRANT	SIDEWALK	62	
TOTAL		957	

AGGREGATE SHOULDERS, TYPE B							48101200
LOCATION	STATION TO STATION	LT/RT	WIDTH FT	DEPTH INCH	CONV. TON/CU YD	QUANTITY	
STA. 100+50.94 TO STA. 134+32.97		LT	2	8	2.05	342	
STA. 100+44.62 TO STA. 134+27.21		RT	2	8	2.05	342	
STA. 134+78.41 TO STA. 151+02.07		LT	2	8	2.05	164	
STA. 134+72.82 TO STA. 151+11.15		RT	2	8	2.05	166	
STA. 152+17.88 TO STA. 179+51.94		LT	2	8	2.05	277	
STA. 152+13.56 TO STA. 179+51.94		RT	2	8	2.05	277	
TOTAL						1568	

MEDIAN REMOVAL			44003100
LOCATION	DESCRIPTION	QUANTITY	
STATION TO STATION		SO FT	
GILES LANE INTERSECTION (RT STA. 151+53)	10' X 8.9'	89	
TOTAL		89	

DETECTABLE WARNINGS						42400800
LOCATION	APPROXIMATE STATION	DESCRIPTION	NUMBER OF DETECTABLE WARNINGS	SIZE EACH	QUANTITY	
					SO FT	
TETON CROSSING - NORTH	134+34	RAMP	2	2' x 3'	12	
TETON CROSSING - SOUTH	134+73	RAMP	2	2' x 3'	12	
GILES CROSSING - NORTH	151+10	RAMP	2	2' x 3'	12	
GILES CROSSING - SOUTH	152+10	RAMP	2	2' x 3'	12	
KNOXVILLE CROSSING - WEST		RAMP	2	2' x 3'	12	
KNOXVILLE CROSSING - EAST		RAMP	2	2' x 3'	12	
TOTAL					72	

PAVEMENT REMOVAL			44000100
LOCATION	DESCRIPTION	QUANTITY	
STATION TO STATION		SO YD	
GILES/KNOXVILLE - NORTH SIDE	PAVEMENT	138	
GILES/KNOXVILLE - SOUTH SIDE	PAVEMENT	195	
TOTAL		334	

PRECAST CONCRETE BOX CULVERT 4' X 2'				54010402
LOCATION	STATION TO STATION	OFFSET FT	QUANTITY	
			FOOT	
STA. 148+12.57 TO STA. 148+44.57		14.40' LT TO 14.82' RT	44	
STA. 152+46.19 TO STA. 152+85.16		18.83' RT TO 15.88' LT	52	
TOTAL			96	

PIPE CULVERTS, CLASS A, TYPE 3 60"			542A1949
LOCATION	LT/RT	QUANTITY	
		FOOT	
STA. 113+72.41	RT	25.6	
STA. 113+88.50	RT	26.1	
TOTAL		52	

PIPE CULVERTS, CLASS D, TYPE 1 12"			54200217
LOCATION	QUANTITY		
	FOOT		
STA. 101+07 (ON SKEW)	38		
TOTAL		38	

END SECTIONS 12"				54213447
LOCATION	OFFSET FT	LT/RT	QUANTITY	
			EACH	
STA. 100+96.08	11.5	LT	1	
STA. 101+25.43	13.5	RT	1	
TOTAL			2	

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"			54213705
LOCATION	LT/RT	QUANTITY	
		EACH	
STA. 113+72.41	RT	1	
STA. 113+88.50	RT	1	
TOTAL		2	

END SECTIONS TO BE REMOVED				X0976500
LOCATION	OFFSET FT	LT/RT	QUANTITY	
STATION			EACH	
STA. 152+46.19	18.83	RT	1	
TOTAL			1	

STORM SEWERS, CLASS A, TYPE 1 12"				550A0050
LOCATION	STATION TO STATION	OFFSET FT	QUANTITY	
			FOOT	
STA. 152+00.00 TO STA. 152+09.00		34.9' RT TO 33.4' RT	9	
TOTAL			9	

INLETS, TYPE G-1				60241800
LOCATION	OFFSET FT	LT/RT	QUANTITY	
			EACH	
STA. 151+98.12	35.21	RT	1	
TOTAL			1	

INLETS TO BE ADJUSTED				60260100
LOCATION	OFFSET FT	LT/RT	QUANTITY	
			EACH	
STA. 152+09.30	33.3	RT	1	
TOTAL			1	

CHAIN LINK FENCE, 5' (SPECIAL)				66400559
LOCATION	STATION TO STATION	LT/RT	QUANTITY	
			FOOT	
STA. 110+00.00 TO STA. 116+00.00		LT	600	
STA. 110+00.00 TO STA. 116+00.00		RT	600	
TOTAL			1200	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS					66600105
LOCATION	STATION	OFFSET FT	LT/RT	QUANTITY	
				EACH	
STA. 112+60.00		50.11	RT	1	
STA. 113+26.77		109.62	RT	1	
STA. 113+60.00		140.00	RT	1	
STA. 114+00.00		140.00	RT	1	
STA. 114+34.69		110.58	RT	1	
STA. 115+00.00		49.12	RT	1	
TOTAL				6	

ENGINEER'S FIELD OFFICE, TYPE B			67000500
LOCATION	QUANTITY		
	CAL MO		
ENTIRE PROJECT	3		
TOTAL		3	

MOBILIZATION			67100100
LOCATION/DESCRIPTION	QUANTITY		
	L SUM		
ENTIRE PROJECT	1		
TOTAL		1	

TRAFFIC CONTROL COMPLETE			70103700
LOCATION/DESCRIPTION	QUANTITY		
	L SUM		
ENTIRE PROJECT	1		
TOTAL		1	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24			60605000
LOCATION	DESCRIPTION	QUANTITY	
STATION		FOOT	
GILES/KNOXVILLE - NORTHWEST QUADRANT	CURB AND GUTTER	161	
GILES/KNOXVILLE - SOUTHWEST QUADRANT	CURB AND GUTTER	221	
GILES/KNOXVILLE - NORTHEAST QUADRANT	CURB AND GUTTER	18	
TOTAL		400	

BOX CULVERT END SECTION, CULVERT NO. 1					54001001
LOCATION	STATION	OFFSET FT	LT/RT	SIZE	QUANTITY
					EACH
STA. 148+12.57		14.40	LT	4' X 2'	1
TOTAL					1

BOX CULVERT END SECTION, CULVERT NO. 2					54001002
LOCATION	STATION	OFFSET FT	LT/RT	SIZE	QUANTITY
					EACH
STA. 148+44.57		14.82	RT	4' X 2'	1
TOTAL					1

BOX CULVERT END SECTION, CULVERT NO. 3					54001003
LOCATION	STATION	OFFSET FT	LT/RT	SIZE	QUANTITY
					EACH
STA. 152+85.16		15.88	LT	4' X 2'	1
TOTAL					1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES ROCK ISLAND/PIMITEOUI BIKE TRAIL SECTION 00-P4002-03-B1 PEORIA COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

