

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
----	00-P4002-03-BT	PEORIA	53	8
STA. 100+36.27		TO STA. 179+51.94		
FED. ROAD DIST. NO. _		ILLINOIS	FED. AID PROJECT	

PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		78001100
LOCATION/DESCRIPTION	QUANTITY	SO FT
TETON DRIVE STA. 134+07 RT	7.83	
TETON DRIVE STA. 134+98 LT	7.83	
GILES LANE STA. 150+72 RT	7.83	
GILES LANE STA. 152+42 LT	7.83	
TOTAL	31	

PAINT PAVEMENT MARKING - LINE 12"		78001150
LOCATION/DESCRIPTION	QUANTITY	FOOT
TETON DRIVE STA. 134+10 RT	5	
TETON DRIVE STA. 134+95 LT	5	
GILES LANE STA. 150+75 RT	5	
GILES LANE STA. 152+39 LT	5	
TOTAL	20	

CONDUIT IN TRENCH, 2" DIA., PVC		81012600
LOCATION	QUANTITY	FOOT
GILES LANE INTERSECTION (RT STA. 152+10)	38	
TOTAL	38	

INCLUDES 3 FOOT SECTION INSTALLED UNDER B-6.24 CC&G
IN ACCORDANCE WITH DETAIL ON STD. 886001-01.

TRENCH AND BACKFILL FOR ELECTRICAL WORK		81500200
LOCATION	QUANTITY	FOOT
GILES LANE INTERSECTION (RT STA. 152+10)	34	
TOTAL	34	

ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 3 PAIR		87301705
LOCATION/DESCRIPTION	QUANTITY	FOOT
GILES INTERSECTION (STA. 152+00)		
CABLE FOR ADDITIONAL DETECTOR LOOPS		
HH SLACK	6.5	
HH TO HH	85.0	
SLACK	6.5	
HH TO HH	85.0	
SLACK	6.5	
HH TO CONTROLLER	16.0	
CONTROLLER FOUNDATION	3.0	
TOTAL	209	

DRILL EXISTING HANDHOLE		87900200
LOCATION	QUANTITY	EACH
GILES LANE INTERSECTION (RT STA. 152+10)	1	
TOTAL	1	

PEDESTRIAN SIGNAL HEAD, LED 88102717 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER		
LOCATION	OFFSET	QUANTITY
	FT	EACH
STA. 150+86.61	7	1
STA. 152+37.32	10	1
TOTAL		2

INDUCTIVE LOOP DETECTOR		88500100
LOCATION	QUANTITY	EACH
GILES LANE INTERSECTION (SE QUADRANT)		
STA. 152+00	3	
TOTAL	3	

DETECTOR LOOP, TYPE I		88600100
LOCATION	QUANTITY	FOOT
GILES LANE INTERSECTION (RT STA. 152+00)		
LOOP 1 (42'+30'+34')	106	
LOOP 2 (42'+18'+34')	94	
LOOP 3 (42'+3'+34')	79	
TOTAL	279	

PEDESTRIAN PUSH-BUTTON				88800100
LOCATION	OFFSET	LT/RT	QUANTITY	EACH
	FT			
STA. 150+86.61	7	RT	1	
STA. 152+37.32	10	RT	1	
TOTAL			2	

MODIFY EXISTING CONTROLLER CABINET		89502210
LOCATION	QUANTITY	EACH
GILES LANE INTERSECTION (SE QUADRANT)	1	
TOTAL	1	

VEHICLE CONTROL BOLLARDS		XX002202
LOCATION	QUANTITY	EACH
STA. 134+12.78 - TETON	1	
STA. 134+92.84 - TETON	1	
STA. 150+78.00 - GILES	1	
STA. 152+36.32 - GILES	1	
TOTAL	4	

CONSTRUCTION LAYOUT		Z0013798
LOCATION	QUANTITY	L SUM
ENTIRE PROJECT	1	
TOTAL	1	



REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES ROCK ISLAND/PIMITEOUI BIKE TRAIL SECTION 00-P4002-03-BT PEORIA COUNTY
SCALE:	VERT. HORIZ.	DRAWN BY
DATE		CHECKED BY