

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 FEDERAL PARTICIPATING	Y060 FEDERAL NON-PARTICIPATING
* B2000770	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3	
* C2003865	ILEX GLABRA SHAMROCK (SHAMROCK INKBERRY), WELL-DEVELOPED, 5 GALLON	EACH	21	21	
Δ * D2C01463	EVERGREEN, JUNIPERUS SABINA BUFFALO (BUFFALO JUNIPER), CONTAINER GROWN, 3-GALLON	EACH	31	31	
* K0012970	PERENNIAL PLANTS, BULB TYPE	UNIT	6.35	6.35	
* K0012980	PERENNIAL PLANTS, ORNAMENTAL TYPE, QUART POT	UNIT	5.50	5.50	
* K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	7.71	7.71	
Δ * X0325846	ABANDONMENT OF EXISTING WATER MAINS	L SUM	1		1
* X2110100	TOPSOIL FURNISH AND PLACE, SPECIAL	CU YD	100	100	
Δ * X5091725	BICYCLE RAILING, SPECIAL	FOOT	144	144	
Δ * X5640175	FIRE HYDRANT COMPLETE	EACH	2	2	
(1) Δ * Z0003850	BENCHES	EACH	3	3	
* Z001378	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	550	550	
* Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	106	106	
* Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	58	58	
* LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	470	470	
* LR430020	PAVING BRICK PAVEMENT FOR HEAVY TRAFFIC	SQ YD	4,063	4,063	
(1) Δ * XX000959	TRASH RECEPTACLES	EACH	12	12	
Δ * XX001987	LINE STOPS 4"	EACH	2		2
Δ * XX004046	AERIAL CABLE REMOVAL	FOOT	2,460	2,460	
Δ * XX004065	LINE STOPS 8"	EACH	1		1
Δ * XX004971	LINE STOPS 6"	EACH	1		1
Δ * XX005049	POWER PEDESTALS	EACH	4	4	
Δ * XX006903	ORNAMENTAL STREET SIGN POST, COMPLETE	EACH	7	7	
Δ * XX007039	STREET LIGHTING ASSEMBLY COMPLETE TYPE F1	EACH	20	20	
Δ * XX007040	STREET LIGHTING ASSEMBLY COMPLETE TYPE F2	EACH	8	8	
Δ * XX007309	BOLLARDS, QUICK RELEASE	EACH	12	12	
Δ * XX008156	LINE STOPS 10"	EACH	1		1
Δ * XX008415	CONCRETE PLANTER BASE	EACH	6	6	
Δ * XX008416	PLANTER - 60" DIA.	EACH	12	12	
Δ * XX008417	PLANTER - 48" DIA.	EACH	3	3	
Δ * XX008418	PLANTER - 30" DIA.	EACH	3	3	
Δ * XX008419	8"x8"x6" TAPPING SLEEVE AND WATER VALVE	EACH	1		1
Δ * XX008420	8"x8"x8" TAPPING SLEEVE AND WATER VALVE	EACH	1		1
* XX008422	BRICK PAVER REMOVAL	SQ YD	5,764	5,764	

\* SEE SPECIAL PROVISIONS  
Δ SPECIALITY ITEMS  
(1)NON-PARTICIPATION/ ITEP

Revised 10/29/10

FILE NAME = Y:\Transportation\2240\22400001.dgn	USER NAME = jolson	DESIGNED - JRB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>CITY OF RUSHVILLE DOWNTOWN SQUARE BRICK STREET RECONSTRUCTION SUMMARY OF QUANTITIES</b>	F.A.U. RTE. N/A	SECTION 05-00017-00-FP	COUNTY SCHUYLER	TOTAL SHEETS 49	SHEET NO. 5	
PLOT SCALE = 2.0000' / IN.	CHECKED - JRB	REVISED -	SCALE: N/A			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			
PLOT DATE = 10/22/2010	DATE - 2/12/2010	REVISED -									