

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 FEDERAL PARTICIPATING	Y060 FEDERAL NON-PARTICIPATING
20200100	EARTH EXCAVATION	CU YD	1,751	1,751	
20800150	TRENCH BACKFILL	CU YD	162	162	
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16	
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16	
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16	
Δ 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5	
Δ • 25200100	SODDING	SQ YD	825	825	
28000500	INLET AND PIPE PROTECTION	EACH	7	7	
28000510	INLET FILTERS	EACH	7	7	
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	7,142	7,142	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	360	360	
35501310	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	SQ YD	2,808	2,808	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,067	1,067	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	95	95	
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	3,358	3,358	
42001300	PROTECTIVE COAT	SQ YD	6,021	6,021	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	23,525	23,525	
42400800	DETECTABLE WARNINGS	SQ FT	280	280	
44000100	PAVEMENT REMOVAL	SQ YD	2,311	2,311	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,123	1,123	
• 44000300	CURB REMOVAL	FOOT	1,030	1,030	
44000600	SIDEWALK REMOVAL	SQ FT	12,986	12,986	
• 44201341	CLASS C PATCHES, TYPE II, 9 INCH	SQ YD	28	28	
Δ • 501125 501125	BICYCLE RAILING, SPECIAL	FOOT	144	144	
55100500	STORM SEWER REMOVAL 12"	FOOT	222	222	
55100900	STORM SEWER REMOVAL 18"	FOOT	69	69	
Δ • 56100600	WATER MAIN 6"	FOOT	722		722
Δ • 56100800	WATER MAIN 10"	FOOT	384		384
Δ • 56104800	WATER VALVES 4"	EACH	32		32
Δ • 56104900	WATER VALVES 6"	EACH	3		3
Δ • 56105000	WATER VALVES 8"	EACH	1		1
Δ • 56105100	WATER VALVES 10"	EACH	1		1
Δ • 56201120	WATER SERVICE LINE 4"	FOOT	310		310
Δ 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	200	200	
Δ • 56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2	2	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	10		10
• 60107600	PIPE UNDERDRAINS 4"	FOOT	1,263	1,263	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	

• SEE SPECIAL PROVISIONS
Δ SPECIALITY ITEMS
(1)NON-PARTICIPATION/ ITEP

FILE NAME = V:\Transportation\2240\22400001.dgn	USER NAME = jolson	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF RUSHVILLE DOWNTOWN SQUARE BRICK STREET RECONSTRUCTION SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JMO	REVISED -			N/A	05-00017-00-FP	SCHUYLER	49	3
		CHECKED - JRB	REVISED -			CONTRACT NO. 93541				
		DATE - 2/12/2010	REVISED -			SCALE: N/A	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 6 [ILLINOIS] FED. AID PROJECT