		CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 FEDERAL PARTICIPATING	Y060 FEDERAL NON-PARTICIPATING
	•	60220230	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1	
		60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1	
	•	60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	2	2	
		60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	2	2	
	•	60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1	1	
	•	60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	9	
	•	60500060	REMOVING INLETS	EACH	3	3	
	•	60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1,042	1,042	
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,450	2,450	
	•	61139800	STORM SEWERS, SPECIAL 4"	FOOT	242	242	
	•	61139900	STORM SEWERS, SPECIAL 6"	FOOT	200	200	
		67100100	MOBILIZATION	L SUM	1	1	
	•	70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	
		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	33	33	
		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,538	7,538	
		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	536	536	
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	165	165	
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,144	3,144	
△	•	72000100	SIGN PANEL - TYPE 1	SQ FT	75	75	
△	•	72800105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	72	72	
△	•	78001100	PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	33	33	
△	•	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4,884	4,884	
△	•	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	536	536	
△	•	78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	141	141	
△	•	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
△		81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	20	20	
△		81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	210	210	
△		81028060	CONDUIT, BORED AND PULLED, COILABLE NON- METALLIC CONDUIT, 2"	FOOT	175	175	
△		81500110	GULFBOX JUNCTION, CAST IRON	EACH	1	1	
△		81500120	GULFBOX, COMPOSITE CONCRETE	EACH	2	2	
△		81603047	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	410	410	
△		81603055	UNIT DUCT, 600V, 3-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2,560	2,560	
△		81603075	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	550	550	
△		81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	80	80	
△		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,750	3,750	
△	•	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1	1	
△		84200804	REMOVAL OF POLE FOUNDATION	EACH	20	20	
△	•	A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3	

• SEE SPECIAL PROVISIONS

△ SPECIALITY ITEMS

(1)NON-PARTICIPATION/ ITEP

FILE NAME = V:\Transportation\2240\22400201.dgn	USER NAME = Jolson	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
		DRAWN - JMO	REVISED -	
	PLOT SCALE = 1.0000 ' / IN.	CHECKED - JRB	REVISED -	
	PLOT DATE = 8/12/2010	DATE - 2/12/2010	REVISED -	

CITY OF RUSHVILLE DOWNTOWN SQUARE BRICK STREET RECONSTRUCTION
SUMMARY OF QUANTITIES

SCALE: N/A | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	05-00017-00-FP	SCHUYLER	49	4

CONTRACT NO. 93541

FED. ROAD DIST. NO. 6 | ILLINOIS | FED. AID PROJECT