

SUMMARY OF QUANTITIES			TOTAL QUANTITIES URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005 ROADWAY 80% FED 20% STATE	0005 ROADWAY 100% STATE			
20200100	EARTH EXCAVATION	CU YD	21	21				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	315	315				
25200110	SODDING, SALT TOLERANT	SO YD	315	315				
25200200	SUPPLEMENTAL WATERING	UNIT	14.2	14.2				
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	68423	68423				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	224	224				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1507	1507				
40604172	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, 1L-9.5, MIX "E", N70	TON	14754	14754				
42001300	PROTECTIVE COAT	SO YD	1692	1692				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1444	1444				
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SO FT	643	643				
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	150544	150544				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		0005 ROADWAY 80% FED 20% STATE	0005 ROADWAY 100% STATE			
44000600	SIDEWALK REMOVAL	SO FT	2086	2086				
44200050	WELDED WIRE REINFORCEMENT	SO YD	719	719				
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SO YD	376	376				
44201023	CLASS B PATCHES, TYPE III, 14 INCH	SO YD	138	138				
44201025	CLASS B PATCHES, TYPE IV, 14 INCH	SO YD	580	580				
44201299	DOWEL BARS 1 1/2"	EACH	1084	1084				
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	3336	3336				
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	669	669				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	2476	2476				
44213200	SAW CUTS	FOOT	3956	3956				
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	7564	7564				
45200300	JOINT OR CRACK FILLING	POUND	2161	2161				
60600605	CONCRETE CURB, TYPE B	FOOT	141	141				
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	73	73				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	62.5	62.5				

FILE NAME = p:\vtdr\mtdr\mtdr\mtdr\Documents\DOT - Offices\Office for Projects\051020\DOT\Design\051020-01-50.dgn

REVISED SHEET 10/26/2021

* = SPECIALTY ITEMS

USER NAME = r/verooj	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100,0000' / 1in	CHECKED -	REVISED -
PLOT DATE = 8/13/2021	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
US 12-20-41 (I-94 TO I-90)**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
29	2020-141-R5	COOK	55	4
CONTRACT NO. 62M19				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	0005 ROADWAY 80% FED 20% STATE	0005 ROADWAY 100% STATE	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3 2	3 2		
63200310	GUARDRAIL REMOVAL	FOOT	73	73		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	21	21		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5		
* 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	LSUM	1	1		
* 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	LSUM	1	1		
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	19	19		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTIONION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTIONION, STANDARD 701602	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70103815	TRAFFIC CONTROL AND SURVEILLANCE	CAL DA	15	15		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	0005 ROADWAY 80% FED 20% STATE	0005 ROADWAY 100% STATE	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	27048	27048		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	9016	9016		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	2476	2476		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37032	37032		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6355	6355		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	319	319		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3562	3562		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	8849	8849		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	7992	7992		
72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2476	2476		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37032	37032		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6355	6355		

REVISED SHEET 10/26/2021
* = SPECIALTY ITEMS

FILE NAME = P:\Users\pawlenko\Documents\DOT - Of fices\Director\Projects\05412020\AD0000\Design\054120-41-500.dgn

USER NAME = r/verooj	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100,0000' / 1"	CHECKED -	REVISED -
PLOT DATE = 8/13/2020	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
US 12-20-41 (I-94 TO I-90)**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
29	2020-141-R5	COOK	55	5
CONTRACT NO. 62M19				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

