

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		047		
61100605	MISCELLANEOUS CONCRETE	CU YD	0.3	0.3		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD	EACH	1	1		
	701321					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	1		
	701201					
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70107005	PAVEMENT MARKING BLACKOUT TAPE, 5"	FOOT	4133	4133		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	315	315		
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	1826	1826		△
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3149	3149		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3149	3149		
70600240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		047		
70600340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2		
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	520	520		
73400100	CONCRETE FOUNDATIONS	CU YD	1.4	1.4		
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	14115	14115		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	36	36		
X0323388	TRAFFIC COUNTER	EACH	1	1		
X5870015	BRIDGE DECK CONCRETE SEALER	SQ FT	22200	22200		
Z0012102	CONCRETE BRIDGE DECK SCARIFICATION 3/8 INCH	SQ YD	15480	15480		
Z0012193	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	15480	15480		
Z0041895	POLYMER CONCRETE	CU FT	7	7		

* SPECIALTY ITEM

△ REVISED 10-15-2021

REV. - MS

MODEL: Default
FILE: M:\MIS\paw\ludect-paw\benefey.com\FIN\DOT\Documents\DOT_Offices\District_7\Projects\74948\CADD\Drawings\CADD\Sheet\DOT74948-sh-500.dgn

USER NAME = steffenmk	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/24/2021	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
827	(12Z-3, 12BR)BDR	WABASH	19	3
			CONTRACT NO. 74948	
ILLINOIS FED. AID PROJECT				