

SUMMARY OF QUANTITIES					FUNDING CATEGORY \ CONSTRUCTION TYPE CODE	
SPECIALTY ITEM	PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	SEC 13-00090-03-RS COVID,STU, STR 0005	SEC 13-00089-02-SD COVID,STR 0005
	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	92		92
	60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2		2
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	7		7
Δ	60218700	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 5 FRAME, OPEN LID	EACH	1		1
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
	60221400	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 5 FRAME, OPEN LID	EACH	1		1
Δ	60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	4		4
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6		6
	60500060	REMOVING INLETS	EACH	1		1
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 **	FOOT	152		152
*	63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	100		100
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2		2
*	66500105	WOVEN WIRE FENCE, 4'	FOOT	1051		1051
	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	10	3	7

SPECIAL PROVISION **



USER NAME =	DESIGNED - KMC	REVISED - Δ 10/20/2021
PLOT SCALE = 2.0000' / in.	DRAWN - KRS DLC	REVISED -
PLOT DATE = 9/1/2021	CHECKED - RDC	REVISED -
	DATE - 01/03/20	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BROADWAY ROAD IMPROVEMENTS
SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF X SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1467	13-00089-02-SD 13-00090-03-RS	TAZEWELL	155	12
CONTRACT NO. 89727			ILLINOIS FED. AID PROJECT 05E2U221	