

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED. 20% STATE	ROADWAY	DRAINAGE (MCDONALD CREEK CULVERT)	LIGHTING	CONSTRUCTION TYPE CODE	
					1000-2A	X078-2A	Y030-1E		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	118	118					
20101100	TREE TRUNK PROTECTION	EACH	5	5					
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	25	25					
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	25					
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	25					
20101700	SUPPLEMENTAL WATERING	UNIT	6	6					
20200100	EARTH EXCAVATION	CU YD	793	793					
20800150	TRENCH BACKFILL	CU YD	213	213					
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	925	925					
25100630	EROSION CONTROL BLANKET	SQ YD	236	236					
25100900	TURF REINFORCEMENT MAT	SQ YD	7	7					
25200110	SOODING, SALT TOLERANT	SQ YD	925	925					
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1					
28000400	PERIMETER EROSION BARRIER	FOOT	177	177					
28000510	INLET FILTERS	EACH	38	38					
28200200	FILTER FABRIC	SQ YD	449	449					
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2,567	2,567					
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	988	988					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,145	1,145					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	42	42					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	97	97					
42001300	PROTECTIVE COAT	SQ YD	1,562	1,562					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	502	502					
44000100	PAVEMENT REMOVAL	SQ YD	4,149	4,149					
44000600	SIDEWALK REMOVAL	SQ FT	502	502					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,697	3,697					
44001980	CONCRETE BARRIER REMOVAL	FOOT	95	95					
44003100	MEDIAN REMOVAL	SQ FT	5,614	5,614					
44003800	MEDIAN SURFACE REMOVAL	SQ FT	2,896	2,896					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	31	31					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1					
50800105	REINFORCEMENT BARS	POUND	121,950	121,950					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	600	600					
50800515	BAR SPLICERS	EACH	312	312					
51205200	TEMPORARY SHEET PILING	SQ FT	1,338	1,338					

FILE NAME =
Gr:\project\2082305\CADD\Civil\Sheet\002\02

USER NAME = 2piensd
2PLMLSM...01.dgn
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 8/11/2009

DESIGNED - DLP
DRAWN - ENTRAN
CHECKED - TMH
DATE - 03/09

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**MCDONALD CREEK CULVERT
SUMMARY OF QUANTITIES**

Rev. 10-22-09

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 305	SECTION 0913.1-T	COUNTY COOK	TOTAL SHEETS 39	SHEET NO. 3
CONTRACT NO. 60E53			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	