

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED.	ROADWAY	DRAINAGE (MCDONALD CREEK CULVERT)	LIGHTING	CONSTRUCTION TYPE CODE	
				20% STATE	1000-2A	X078-2A	Y030-1E		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	399		399				
* 72000100	SIGN PANEL - TYPE 1	SQ FT	43		43				
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8		8				
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	59		59				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6,190		6,190				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,269		1,269				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	32		32				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	160		160				
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4		4				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1		1				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,333		3,333				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	160		160				
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	277	277					
* 81400100	HANDHOLE	EACH	1	1					
* 81603120	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (EPR-TYPE RHW), 3/4" DIA. POLYETHYLENE	FOOT	174			174			
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,618			1,618			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	422	254		168			
* 82102200	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 200 WATT	EACH	3			3			
* 83057225	LIGHT POLE, WOOD, 40 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	3			3			
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	30			30			
* 83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	3			3			
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	3			3			
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2				
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	2,806	2,806					
* 89502200	MODIFY EXISTING CONTROLLER	EACH	2		2				
* 89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1,273	1,273					
* 89502380	REMOVE EXISTING HANDHOLE	EACH	1		1				
* 89502390	TEMPORARY INFORMATION SIGNING	SQ FT	32	32					
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	32		32				
* X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	5			5			
* X0323651	REMOVE AND REINSTALL EXISTING LIGHTING UNIT	EACH	3			3			
* X0325134	WIRELESS INTERCONNECT (COMPLETE)	EACH	1	1					
X0712400	TEMPORARY PAVEMENT	SQ YD	3,160		3,160				
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1.0		1.0				
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 4 INCH	FOOT	15,376		15,376				
X7030108	WET TEMPORARY PAVEMENT MARKING TAPE , TYPE III, 8 INCH	FOOT	2,786		2,786				

* Specialty Items

Rev. 10-22-09