

| SUMMARY OF QUANTITIES |   |       |       | 80% FEDERAL, 20% STATE |                | SUMMARY OF QUANTITIES |  |        |                  | 80% FEDERAL, 20% STATE |                |
|-----------------------|---|-------|-------|------------------------|----------------|-----------------------|--|--------|------------------|------------------------|----------------|
| CODE NO.              | ITEM  | UNIT  | TOTAL | ROADWAY 1000           | BRIDGE X281-2A | CODE NO.              | ITEM   | UNIT   | TOTAL QUANTITIES | ROADWAY 1000           | BRIDGE X281-2A |
| 20200100              | EARTH EXCAVATION                              | CU YD | 99    | 99                     |                | 50104720              | REMOVAL OF EXISTING CONCRETE DECK                        | EACH   | 1                |                        | 1              |
| 20700400              | POROUS GRANULAR EMBANKMENT, SPECIAL           | CU YD | 38    |                        | 38             | 50157300              | PROTECTIVE SHIELD  | SQ YD  | 49               |                        | 49             |
| 21101815              | COMPOST FURNISH AND PLACE, 4"                 | SQ YD | 984   | 984                    |                | 50200100              | STRUCTURE EXCAVATION                                     | CU YD  | 38               |                        | 38             |
| 25000310              | SEEDING, CLASS 4                              | ACRE  | 0.2   | 0.2                    |                | 50300225              | CONCRETE STRUCTURES                                      | CU YD  | 25.9             |                        | 25.9           |
| 25000400              | NITROGEN FERTILIZER NUTRIENT                  | POUND | 18    | 18                     |                | 50300255              | CONCRETE SUPERSTRUCTURE                                  | CU YD  | 170.9            |                        | 170.9          |
| 25000500              | PHOSPHORUS FERTILIZER NUTRIENT                | POUND | 18    | 18                     |                | 50300260              | BRIDGE DECK GROOVING                                     | SQ YD  | 395.6            |                        | 395.6          |
| 25000600              | POTASSIUM FERTILIZER NUTRIENT                 | POUND | 18    | 18                     |                | 50300300              | PROTECTIVE COAT  | SQ YD  | 459.5            |                        | 459.5          |
| 25100630              | EROSION CONTROL BLANKET                       | SQ YD | 984   | 984                    |                | 50500405              | FURNISHING AND ERECTING STRUCTURAL STEEL                 | POUND  | 2100             |                        | 2100           |
| 28000250              | TEMPORARY EROSION CONTROL SEEDING             | POUND | 20    | 20                     |                | 50500505              | STUD SHEAR CONNECTORS                                    | EACH   | 819              |                        | 819            |
| 28000300              | TEMPORARY DITCH CHECKS                        | EACH  | 4     | 4                      |                | 50600300              | CLEANING AND PAINTING STEEL BRIDGE                       | L SUM  | 1                |                        | 1              |
| 28000400              | PERIMETER EROSION BARRIER                     | FOOT  | 806   | 806                    |                | 50606400              | CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES | L SUM  | 1                |                        | 1              |
| 28100109              | STONE RIPRAP, CLASS A5                        | SQ YD | 378   |                        | 378            | 50800205              | REINFORCEMENT BARS, EPOXY COATED                         | POUND  | 43050            |                        | 43050          |
| 28200200              | FILTER FABRIC                                 | SQ YD | 378   |                        | 378            | 50800515              | BAR SPLICERS   | EACH   | 440              |                        | 440            |
| 40600200              | BITUMINOUS MATERIALS (PRIME COAT)             | TON   | 1     | 1                      |                | 51500100              | NAME PLATES  | EACH   | 1                |                        | 1              |
| 40600635              | LEVELING BINDER (MACHINE METHOD), N70         | TON   | 43    | 43                     |                | 52100520              | ANCHOR BOLTS, 1"   | EACH   | 28               |                        | 28             |
| 40600300              | AGGREGATE (PRIME COAT)                        | TON   | 3     | 3                      |                | 59000200              | EPOXY CRACK INJECTION                                    | FOOT   | 5                |                        | 5              |
| 40600400              | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS    | TON   | 1     | 1                      |                | 59100100              | GEOCOMPOSITE WALL DRAIN                                  | SQ YD  | 25               |                        | 25             |
| 40600982              | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT  | SQ YD | 29    | 29                     |                | 60109580              | PIPE UNDERDRAINS FOR STRUCTURES 4"                       | FOOT   | 186              |                        | 186            |
| 40601005              | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES      | TON   | 28    | 28                     |                | * 63000001            | STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS        | FOOT   | 63               | 63                     |                |
| 40603340              | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70  | TON   | 64    | 64                     |                | * 63100085            | TRAFFIC BARRIER TERMINAL, TYPE 6                         | EACH   | 4                | 4                      |                |
| 42001430              | BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) | SQ YD | 59    | 59                     |                | * 63100167            | TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT       | EACH   | 3                | 3                      |                |
| 44000100              | PAVEMENT REMOVAL                              | SQ YD | 274   | 274                    |                | 66502300              | WOVEN WIRE FENCE REMOVAL                                 | FOOT   | 279              | 279                    |                |
| 44000159              | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"       | SQ YD | 589   | 589                    |                | 67000400              | ENGINEER'S FIELD OFFICE, TYPE A                          | CAL MO | 9                | 9                      |                |
| 44000700              | APPROACH SLAB REMOVAL                         | SQ YD | 160   |                        | 160            | 67100100              | MOBILIZATION   | L SUM  | 1                | 1                      |                |
| 44201753              | CLASS D PATCHES, TYPE II, 9 INCH              | SQ YD | 75    | 75                     |                | 70100400              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701431          | EACH   | 1                | 1                      |                |
| 44201757              | CLASS D PATCHES, TYPE III, 9 INCH             | SQ YD | 90    | 90                     |                | 70100405              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321          | EACH   | 1                | 1                      |                |
| 44300200              | STRIP REFLECTIVE CRACK CONTROL TREATMENT      | FOOT  | 448   | 448                    |                | 70100500              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326          | L SUM  | 1                | 1                      |                |
| 48102100              | AGGREGATE WEDGE SHOULDER, TYPE B              | TON   | 49    | 49                     |                | 70101800              | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)                | L SUM  | 1                | 1                      |                |
| 48203013              | HOT-MIX ASPHALT SHOULDERS, 4"                 | SQ YD | 101   | 101                    |                | 70103815              | TRAFFIC CONTROL SURVEILLANCE                             | CAL DA | 156              | 156                    |                |

\* SPECIALTY ITEMS

\* Specialty Items

**LONCO INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

|                   |           |
|-------------------|-----------|
| DESIGNED - MJY    | REVISED - |
| DRAWN - ST        | REVISED - |
| CHECKED - MJY     | REVISED - |
| DATE - 09/09/2009 | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
I-55 WEST FRONTAGE ROAD OVER (I & M) CANAL**

SCALE: NONE SHEET NO. 3 OF 38 SHEETS STA. 1097+00 TO STA. 1101+50

|                     |          |                           |                    |           |
|---------------------|----------|---------------------------|--------------------|-----------|
| F.A.I. RTE.         | SECTION  | COUNTY                    | TOTAL SHEETS       | SHEET NO. |
| 55                  | 86 B-3-R | WILL                      | 38                 | 3         |
| D-91-097-09         |          |                           | CONTRACT NO. 60F53 |           |
| FED. ROAD DIST. NO. |          | ILLINOIS FED. AID PROJECT |                    |           |